IEEE Std 1802.3-2001 (Revision of IEEE Std 1802.3-1991, includes IEEE Std 1802.3d-1993)

IEEE Conformance Test Methodology for IEEE Standards for Local and Metropolitan Area Networks—

Specific Requirements—Part 3: Carrier Sense Multiple Access with Collision Detection (CSMA/CD) Access Method and Physical Layer Specifications

IEEE Computer Society

Sponsored by the LAN/MAN Standards Committee



Published by The Institute of Electrical and Electronics Engineers, Inc. 3 Park Avenue, New York, NY 10016-5997, USA

19 October 2001

Print: SH94957 PDF: SS94957

IEEE Conformance Test Methodology for IEEE Standards for Local and Metropolitan Area Networks—

Specific Requirement—Part 3: Carrier Sense Multiple Access with Collision Detection (CSMA/CD) Access Method and Physical Layer Specifications

Sponsor

LAN/MAN Standards Committee of the IEEE Computer Society

Approved 10 October 2001

IEEE-SA Standards Board

Abstract: Abstract methods for the conformance testing of 802.3 Clause 14 (10BASE-T MAU) implementations in order to satisfy conformance requirements arising from the ISO/IEC 8802-3 (IEEE Std 802.3) specification are provided.

Keywords: AUI, compliance, conformance testing, MAC, MAU, PICS, PIXIT, PLS

Print: ISBN 0-7381-3010-9 SH94957 PDF: ISBN 0-7381-3011-9 SS94957

The Institute of Electrical and Electronics Engineers, Inc. 3 Park Avenue, New York, NY 10016-5997, USA

Copyright © 2001 by the Institute of Electrical and Electronics Engineers, Inc. All rights reserved. Published 19 October 2001. Printed in the United States of America.

No part of this publication may be reproduced in any form, in an electronic retrieval system or otherwise, without the prior written permission of the publisher.

IEEE Standards documents are developed within the IEEE Societies and the Standards Coordinating Committees of the IEEE Standards Association (IEEE-SA) Standards Board. The IEEE develops its standards through a consensus development process, approved by the American National Standards Institute, which brings together volunteers representing varied viewpoints and interests to achieve the final product. Volunteers are not necessarily members of the Institute and serve without compensation. While the IEEE administers the process and establishes rules to promote fairness in the consensus development process, the IEEE does not independently evaluate, test, or verify the accuracy of any of the information contained in its standards.

Use of an IEEE Standard is wholly voluntary. The IEEE disclaims liability for any personal injury, property or other damage, of any nature whatsoever, whether special, indirect, consequential, or compensatory, directly or indirectly resulting from the publication, use of, or reliance upon this, or any other IEEE Standard document.

The IEEE does not warrant or represent the accuracy or content of the material contained herein, and expressly disclaims any express or implied warranty, including any implied warranty of merchantability or fitness for a specific purpose, or that the use of the material contained herein is free from patent infringement. IEEE Standards documents are supplied "AS IS."

The existence of an IEEE Standard does not imply that there are no other ways to produce, test, measure, purchase, market, or provide other goods and services related to the scope of the IEEE Standard. Furthermore, the viewpoint expressed at the time a standard is approved and issued is subject to change brought about through developments in the state of the art and comments received from users of the standard. Every IEEE Standard is subjected to review at least every five years for revision or reaffirmation. When a document is more than five years old and has not been reaffirmed, it is reasonable to conclude that its contents, although still of some value, do not wholly reflect the present state of the art. Users are cautioned to check to determine that they have the latest edition of any IEEE Standard.

In publishing and making this document available, the IEEE is not suggesting or rendering professional or other services for, or on behalf of, any person or entity. Nor is the IEEE undertaking to perform any duty owed by any other person or entity to another. Any person utilizing this, and any other IEEE Standards document, should rely upon the advice of a competent professional in determining the exercise of reasonable care in any given circumstances.

Interpretations: Occasionally questions may arise regarding the meaning of portions of standards as they relate to specific applications. When the need for interpretations is brought to the attention of IEEE, the Institute will initiate action to prepare appropriate responses. Since IEEE Standards represent a consensus of concerned interests, it is important to ensure that any interpretation has also received the concurrence of a balance of interests. For this reason, IEEE and the members of its societies and Standards Coordinating Committees are not able to provide an instant response to interpretation requests except in those cases where the matter has previously received formal consideration.

Comments for revision of IEEE Standards are welcome from any interested party, regardless of membership affiliation with IEEE. Suggestions for changes in documents should be in the form of a proposed change of text, together with appropriate supporting comments. Comments on standards and requests for interpretations should be addressed to:

Secretary, IEEE-SA Standards Board 445 Hoes Lane P.O. Box 1331 Piscataway, NJ 08855-1331 USA

Note: Attention is called to the possibility that implementation of this standard may require use of subject matter covered by patent rights. By publication of this standard, no position is taken with respect to the existence or validity of any patent rights in connection therewith. The IEEE shall not be responsible for identifying patents for which a license may be required by an IEEE standard or for conducting inquiries into the legal validity or scope of those patents that are brought to its attention.

IEEE is the sole entity that may authorize the use of certification marks, trademarks, or other designations to indicate compliance with the materials set forth herein.

Authorization to photocopy portions of any individual standard for internal or personal use is granted by the Institute of Electrical and Electronics Engineers, Inc., provided that the appropriate fee is paid to Copyright Clearance Center. To arrange for payment of licensing fee, please contact Copyright Clearance Center, Customer Service, 222 Rosewood Drive, Danvers, MA 01923 USA; (978) 750-8400. Permission to photocopy portions of any individual standard for educational classroom use can also be obtained through the Copyright Clearance Center.

Introduction to IEEE Std 1802.3-2001

[This introduction is not part of IEEE Std 1802.3-2001, IEEE Conformance Test Methodology for IEEE Standards for Local and Metropolitan Area Networks—Specific Requirements—Part 3: Carrier Sense Multiple Access with Collision Detection (CSMA/CD) Access Method and Physical Layer Specifications.]

This standard is part of a family of standards for local and metropolitan area networks. The relationship between the standard and other members of the family is shown below. (The numbers in the figure refer to IEEE standard numbers.)



* Formerly IEEE Std 802.1A.

This family of standards deals with the Physical and Data Link layers as defined by the International Organization for Standardization (ISO) Open Systems Interconnection (OSI) Basic Reference Model (ISO/IEC 7498-1: 1994). The access standards define seven types of medium access technologies and associated physical media, each appropriate for particular applications or system objectives. Other types are under investigation.

The standards defining the technologies noted above are as follows:

•	IEEE Std 802	<i>Overview and Architecture</i> . This standard provides an overview to the family of IEEE 802 Standards.
•	ANSI/IEEE Std 802.1B and 802.1k [ISO/IEC 15802-2]	<i>LAN/MAN Management</i> . Defines an OSI management-compatible architecture, and services and protocol elements for use in a LAN/MAN environment for performing remote management.
•	ANSI/IEEE Std 802.1D	<i>Media Access Control (MAC) Bridges.</i> Specifies an architecture and protocol for the interconnection of IEEE 802 LANs below the MAC service boundary.
•	ANSI/IEEE Std 802.1E [ISO/IEC 15802-4]	<i>System Load Protocol</i> . Specifies a set of services and protocol for those aspects of management concerned with the loading of systems on IEEE 802 LANs.
•	ANSI/IEEE Std 802.1F	Common Definitions and Procedures for IEEE 802 Management Information.
•	ANSI/IEEE Std 802.1G [ISO/IEC 15802-5]	<i>Remote Media Access Control (MAC) Bridging</i> . Specifies extensions for the interconnection, using non-LAN communication technologies, of geographically separated IEEE 802 LANs below the level of the logical link control protocol.
•	IEEE Std 802.1H [ISO/IEC TR 11802-5]	Media Access Control (MAC) Bridging of Ethernet V2.0 in Local Area Networks.
•	ANSI/IEEE Std 802.2	Logical Link Control.

[ISO/IEC 8802-2]

- ANSI/IEEE Std 802.3 CSMA/CD Access Method and Physical Layer Specifications.
- ANSI/IEEE Std 802.4 Token Passing Bus Access Method and Physical Layer Specifications. [ISO/IEC 8802-4]
- ANSI/IEEE Std 802.5 *Token Ring Access Method and Physical Layer Specifications*. [ISO/IEC 8802-5]
- ANSI/IEEE Std 802.6 Distributed Queue Dual Bus Access Method and Physical Layer [ISO/IEC 8802-6] Specifications.
- ANSI/IEEE Std 802.10 Interoperable LAN/MAN Security.
- ANSI/IEEE Std 802.11 Wireless LAN Medium Access Control (MAC) and Physical Layer
 [ISO/IEC DIS 8802-11] Specifications.
- ANSI/IEEE Std 802.12 Demand Priority Access Method, Physical Layer and Repeater [ISO/IEC 8802-12] Specifications.

In addition to the family of standards, the following is a recommended practice for a common Physical Layer technology:

• IEEE Std 802.7 IEEE Recommended Practice for Broadband Local Area Networks.

Conformance test methodology

An additional standards series, identified by the number 1802, was established to identify the conformance test methodology documents for the 802 family of standards. This makes the correspondence between the various 802 standards and their applicable conformance test requirements readily apparent. Thus the conformance test document for 802.3 is numbered 1802.3.

IEEE Std 1802.3-2001

This standard, IEEE Std 1802.3-2001 is a revision of IEEE Std 1802.3-1991 and IEEE Std 1802.3d-1993. This standard provides conformance test information to satisfy requirements for certain implementations of 10BASE-T arising from ISO/IEC 8802-3: 2000 (IEEE Std 802.3, 2000 Edition). At the time this standard was approved, the complete IEEE 802.3 family of standards consisted of the following published documents:

ISO/IEC 8802-3: 2000 (IEEE Std 802.3, 2000 Edition)

Information on the current revision state of this, IEEE Std 802.3 and other IEEE 802 standards may be obtained from Secretary, IEEE Standards Board P.O. Box 1331 445 Hoes Lane Piscataway, NJ 08855-1331, USA

IEEE 802 committee working documents are available from IEEE Draft Service P.O. Box 1331 445 Hoes Lane Piscataway, NJ 08855-1331, USA

http://standards.ieee.org/

At the time the 802.3 Working Group approved IEEE Std 1802.3-2001, it had the following membership:

Geoffrey O. Thompson, Chair

David J. Law, Vice Chair

Oscar Agazzi Don Alderrou Khaled Amer Arlan J. Anderson Ralph Andersson Ken-ichi Arai Kameran Azadet Vipul D. Badoni Keith Balmer Denis Beaudoin Mike Bennett John L. Bestel Michel Bohbot Brad Booth Paul Bottorff Gary Bourque Benjamin Brown Lisa Buckman Scott Burton Robert Busse Roy Bynum Richard Cam Bob Campbell Steve Carlson Edward G. Chang Edward S. Chang Zinan Chen Hon Wah Chin Terry Cobb Régis Colla Edward Cornejo John Creigh Kevin Daines Piers Dawe Tom Debiec Chris Di Minico Erik Dickens Thomas Dineen Allen Dixon Mark Donhowe Dan Dove Steve Dreyer Richard Dugan George Eisler John F. Ewen Jens Fiedler Norival Figueira Alan Flatman Howard Frazier Scott Fritz Darrell Furlong Tim Ganley Giorgio Giaretta Joel Goergen

Moty Goldis Rich Graham Robert M. Grow Stephen Haddock Atikem Haile-Mariam Del Hanson Doug Harshbarger Lloyd Hasley Marwan Hassoun John F. Hawkins Gaby Hecht Ken Herrity Henry Hinrichs Ernie Jensen Clarence Joh Thomas K. Jørgensen Juan Jover Shinkyo Kaku Mohan Kalkunte Amrit Kalla Hadriel Kaplan Jaime Kardontchik Dennis L. Karst Toyoyuki Kato Paul Kolesar Josef Kosilek Hans Lackner Daun Langston Loren Larsen Brian E. Lemoff George Lin Fred A. Lucas Jeffrey Lynch Brian MacLeod Robert A. Marsland David W. Martin Thomas Mathey Michael S. McCormack Tremont Miao Colin Mick Larry D. Miller Dirk S. Mohl Cindy Montstream Robert Mortonson Shimon Muller Denis Murphy Robert Musk Yaron Nachman Ken Naganuma Hari Naidu Paul Nikolich Michael Nootbaar Bob Noseworthy Mark Nowell

Satoshi Obara Toshio Ooka Don Pannell Joel Paslaski John Payne Timothy R. Plunkett Bernd Prediger William Quackenbush Brian Ramelson Peter Rautenberg Anil Rijsinghani Carlos Rodriguez Shawn Rogers Floyd Ross Larry Rubin Simon Sabato Michael M. Salzman **Bill Sarles** Ted Schroeder **Rich Seifert** Lee Sendelbach Koichiro Seto Som Sikdar Michael A. Smith David Sorensen Michel Sørensen Nick Stapleton Ronald Steudler Stephen Strong Steve Swanson Tad Szostak Rich Taborek R. Jonathan Thatcher Walter Thirion Douglas Thomson Bruce Tolley Edward Turner Schelto van Doorn John Van Gilder Dono Van-Mierop Iain Verigin Nader Vijeh Bill Villamor Greg Wang Peter Wang Fred Weniger Willem Wery Joris Wils Mike Witkowski David Wong Chong Ho Yoon Leonard Young Ben Yu Mark (Meng-Lin) Yu

The following members of the balloting committee voted on this standard. Balloters may have voted for approval, disapproval, or abstention:

Terry S. Arnold Jacob Ben Arv James T. Carlo Keith Chow Thomas J. Dineen Christos Douligeris John W. Fendrich Howard M. Frazier Robert M. Grow Chris G. Guy Robert J. Hughes David J. Law Randolph S. Little James S. Marin Peter Martini Richard McBride Bennett Meyer Robert Mortonson Roger Pandanda Kenneth L. Peirce Vikram Punj Stephen M. Reis Edouard Y. Rocher Floyd E. Ross Rich Seifert Robert C. Tripi Edward Turner Mark-Rene Uchida Scott A. Valcourt Forrest D. Wright

When the IEEE-SA Standards Board approved this standard on 10 October 2001, it had the following membership:

Donald N. Heirman, *Chair* **James T. Carlo,** *Vice Chair* **Judith Gorman,** *Secretary*

Chuck Adams Mark D. Bowman Clyde R. Camp Richard DeBlasio Harold E. Epstein H. Landis Floyd Jay Forster* Howard M. Frazier James H. Gurney Raymond Hapeman Richard J. Holleman Richard H. Hulett Lowell G. Johnson Joseph L. Koepfinger* Peter H. Lips Paul J. Menchini Daleep C. Mohla Robert F. Munzner Ronald C. Petersen Malcolm V. Thaden Geoffrey O. Thompson Akio Tojo Howard L. Wolfman

*Member Emeritus

Also included is the following nonvoting IEEE-SA Standards Board liaisons:

Satish K. Aggarwal, *NRC Representative* Alan H. Cookson, *NIST Representative* Donald R. Volzka, *TAB Representative*

> Catherine Berger IEEE Standards Project Editor

The marks "**IEEE**" and "**802**" are registered trademarks belonging to the IEEE. When using these marks to refer to The Institute of Electrical and Electronics Engineers, **802** standards or other standards, the marks should be in bold typeface and, at least once in text, use the registered trademark symbol "®".

Contents

1.	Introduction	. 1
	1.1 Purpose	. 1
	1.2 Scope	
	1.3 Acronyms and abbreviations	
	1.4 Overview	
	1.5 Test case header description	. 3
	1.6 Numbering scheme	. 4
	1.7 Verdict assignment	
	1.8 References	. 5
2.	MAC conformance testing	. 5
3.	PLS conformance testing	. 5
4.	AUI Cable conformance testing	. 5
5.	10BASE5 MAU conformance testing	. 6
6.	Type 10BASE-T MAU conformance test methodology	. 6
	6.1 Scope of 10BASE-T MAU conformance test	. 6
	6.2 10BASE-T MAU abstract test suite	
	6.3 Test setups, signals, and adapters description	53
Anney	A (informative) Reference information	30

IEEE Conformance Test Methodology for IEEE Standards for Local and Metropolitan Area Networks—

Specific Requirements—Part 3: Carrier Sense Multiple Access with Collision Detection (CSMA/CD) Access Method and Physical Layer Specifications

1. Introduction

1.1 Purpose

This standard defines abstract methods for the conformance testing of 802.3 Clause 14 (10BASE-T MAU) implementations in order to satisfy conformance requirements arising from ISO/IEC 8802-3¹ [IEEE Std 802.3]. Such methods will form the basis for any subsequent development of executable test cases.

1.2 Scope

The conformance test suite is intended to detect incorrect implementations of Clause 14 (10BASE-T MAU) of the ISO/IEC 8802-3 standard [IEEE Std 802.3] with the exception of the options that have been added to Clause 14 since the publication of 1996 edition of ISO/IEC 8802-3 [IEEE Std 802.3]. The Clause 14 options excluded from this conformance test suite are support for Auto-Negotiation and full-duplex operation. The test suite should demonstrate conformance to Clause 14 of the ISO/IEC 8802-3 standard [IEEE Std 802.3]. However, the user should be made aware of Section 1.3, paragraph 2, of the IEEE Standards Manual, December 1990 edition (Conformance of Products or Systems to IEEE Standards):

IEEE Standards may contain testing procedures useful in determining whether products or systems are in compliance with the standards. Compliance in itself does not necessarily imply quality or guarantee proper use. Where IEEE Standards are used as the basis of examination and/or testing of products or systems by laboratories or other agencies in the process of determining their suitability for their intended use and safe operation, the IEEE assumes no responsibility for the use or interpretation of its standards or the adequacy of the testing or certification.

The test setups and procedure described in this standard are designed to provide the implementor with a methodology for obtaining repeatable results by which conformance can be judged. However, these methodologies are by no means unique. This standard does not preclude the use of alternative methodologies provided that an equivalence between the prescribed methodology and the alternative methodology can be demonstrated.

¹Information on references can be found in 1.8.

It is acknowledged that conformance testing may need to be augmented by other testing (i.e., interoperability or development testing). Such testing is beyond the scope of this standard. It is possible, on the other hand, that an implementation may be interoperable with other implementations but not satisfy conformance testing.

Finally the reader should note that no environmental specifications appear in the test suite. A prudent vendor should ensure that the implementation operates as intended throughout the vendor s specified environmental range before claiming conformance.

1.3 Acronyms and abbreviations

ANSI	American National Standards Institute
ATS	abstract test suite
AUI	attachment unit interface
AWG	arbitrary waveform generator
BAL	balanced-unbalanced matching transformer (Balun)
BT	bit time
CI	control in circuit
СР	current probe
CO	control out circuit
CSMA/CD	carrier sense multiple access/collision detect
dB	decibels
DI	data in circuit
DIS	draft international standard
DP	differential probe
DO	data out circuit
DTE	data terminal equipment
FG	function generator
HDP	high-performance differential probe
IDL	idle signal
IEEE	Institute of Electrical and Electronics Engineers
IEC	International Electrotechnical Commission
ISO	International Organization for Standardization
IUT	implementation under test
kHz	kilohertz
LTPG	link test pulse generator
MAC	media access control
MAU	medium attachment unit
Mb/s	megabits per second
MDI	medium dependent interface
MHz	megahertz
OSI	open systems interconnection
PG	protective ground
PICS	protocol implementation conformance statement
PIXIT	protocol implementation extra information for testing

PLS	physical signaling
RD	receive data
RM	reference model
SFD	start frame delimiter
SOI	start of idle
SQE	signal_quality_error
TBD	to be defined
TD	transmit data
TPG	test pattern generator
TPM	twisted-pair model
VP	voltage plus
VC	voltage common

1.4 Overview

Clause 6 of this standard is organized into two main subclauses. These subclauses are as follows:

- a) Abstract test suite. This is comprised of two categories of test groups. The first category involves basic interconnection testing; the second concerns capability and behavior testing. Within both categories are a number of test groups, where each group is aimed at collecting individual test cases that share some communality in features tested or test methods used. The format of this standard is meant to be consistent with guidelines for ISO Conformance Test Methodology. The reader is advised to review ISO/IEC 9646.
- b) **Test setups and adapters description.** This subclause describes the test setups, adapters, and instruments used in the abstract test suite.

1.5 Test case header description

Each test case is written in a standard format. This subclause defines the various fields of the standard format.

Test Case ID	: Identification number given to the test case. See 1.6 for encoding of the test case identi- fications.
Test Case Name	: Name assigned to the test case.
Status	: Indicates level of conformance required. May be <i>Mandatory</i> or <i>Optional</i> . Mandatory requirements are to be observed in all cases. Optional requirements are to be observed when conditions set out in the standard apply.
Standard Ref.	: Clause of ISO/IEC 8802-3 [IEEE Std 802.3] standard.
History	: Additional reference to approved revisions to the standard.
Test Purpose	: Purpose(s) of the test case.
Note	: Additional information may be provided in this section.
Test Setup	: This section describes the test setup. The detailed test setup is defined in each conform- ance test section.

Test Procedure : This section describes the test procedure.

Conformance : Statement of conformance requirement, usually quoted directly from the standard.

1.6 Numbering scheme

This is the test-case numbering scheme as used by the ISO/IEC 8802-3 [IEEE Std 802.3] conformance test specifications. Some of the evolving test suites and their corresponding numbers are given as follows:

MAC	2111
PLS	1311
AUI cable	1211
10BASE5 MAU	1111
10BASE-T MAU	1411

The form is as follows:

ABCD.EF.GH

where

- A Layer
- B Sublayer Reference
- C Class or Access Method
- D. Transmission Variant or Classification
- EF. Test Group Number
- GH Test Case Number

Example: 1411.07.01 refers to test case 01 in test group 07 of the test suite for the CSMA/CD physical layer testing 10BASE-T MAU component.

1411.EF.GH

where

- 1 = Physical layer
- 4 = 10BASE-T MAU
- 1 = CSMA/CD (medium independent)
- 1 = 10 Mb/s

1.7 Verdict assignment

It is recognized that a conformance verdict may depend on the accuracy of a test measurement and the capabilities of an instrument. The abstract test procedure does not specify accuracy requirements. An executable test suite derived from the abstract test suite shall state the accuracy of each measurement in a test case. The verdict shall be inconclusive if derived without the necessary measurement accuracy.

1.8 References

This standard shall be used with the following publications. When the following publications are superseded by an approved revision, the revision shall apply.

ISO 7498:1984, Information Processing Systems — Open Systems Interconnection — Basic Reference Model.²

ISO/IEC 9646:1994, Information processing systems — Open systems interconnection — OSI conformance testing methodology and framework.

ISO/IEC 8802-3:2000 [IEEE Std 802.3, 2000 Edition], Information Technology — Local and Metropolitan Area Networks — Part 3: Carrier Sense Multiple Access with Collision Detection (CSMA/CD) Access Method and Physical Layer Specifications.³

IEC 60060, High-Voltage Test Techniques.⁴

IEC 60096-1:1986, Radio-Frequency Cables, Part 1: General Requirements and Measuring Methods.

IEC 600950:1991, Safety of Information Technology Equipment, Including Electrical BusinessEquipment.

IEC 60603-7:1999, Connectors for Frequencies Below 3 MHz for Use with Printed Boards, Part 7: Detail Specification for Connectors, 8-way, Including Fixed and Free Connectors with Common Mating Features, with Assessed Quality.

IEC 60807-2:1985 (1st Edition), Rectangular Connectors for Frequencies Below 3 MHz, Part 2: Detail Specification for a Range of Connectors with Round Contacts — Fixed Solder Contact Types.

2. MAC conformance testing

Clause 2 was originally reserved for MAC conformance testing. No further work is planned on this standard.

3. PLS conformance testing

Clause 3 was originally reserved for PLS conformance testing. No further work is planned on this standard.

4. AUI Cable conformance testing

Clause 4 originally contained information on AUI Cable conformance testing. No further work is planned on this standard.

²ISO publications are available from the ISO Central Secretariat, Case Postale 56, 1 rue de Varemb, CH-1211, Gen ve 20, Switzerland/Suisse (http://www.iso.ch/). ISO publications are also available in the United States from the Sales Department, American National Standards Institute, 11 West 42nd Street, 13th Floor, New York, NY 10036, USA (http://www.ansi.org/).

³IEEE publications are available from the Institute of Electrical and Electronics Engineers, 445 Hoes Lane, P.O. Box 1331, Piscataway, NJ 08855-1331, USA (http://standards.ieee.org/).

⁴In the 2001 edition of this standard, IEC publications have been renumbered in accordance with IEC s revised numbering system. In 1997, all existing publications were issued a designation in the 60000 series. Thus IEC 60 became IEC 60060, IEC 950 became IEC 60950, etc. IEC publications are available from the Sales Department of the International Electrotechnical Commission, Case Postale 131, 3, rue de Varemb, CH-1211, Gen ve 20, Switzerland/Suisse (http://www.iec.ch/). IEC publications are also available in the United States from the Sales Department, American National Standards Institute, 11 West 42nd Street, 13th Floor, New York, NY 10036, USA.

5. 10BASE5 MAU conformance testing

Clause 5 was originally reserved for 10BASE5 MAU conformance testing. No further work is planned on this standard.

6. Type 10BASE-T MAU conformance test methodology

6.1 Scope of 10BASE-T MAU conformance test

The purpose of this clause is to define abstract methods for the conformance testing of 10BASE-T MAU implementations in order to satisfy conformance requirements arising from the 10BASE-T MAU specification (Clause 14 of ISO/IEC 8802-3) with the exception of the options that have been added to Clause 14 since the publication of 1996 edition of ISO/IEC 8802-3 [IEEE Std 802.3]. The Clause 14 options excluded from this conformance test suite are support for Auto-Negotiation and full-duplex operation however full coverage of operation at the MDI is provided. Such methods will form the basis for any subsequent development of executable test cases. This standard is applicable to the conformance testing of CSMA/CD 10BASE-T MAU (hereafter referred to as MAU) implementations that have been designed to Clause 14 of ISO/IEC 8802-3. Additional information about the implementation under test may be found in the Protocol Implementation Extra Information for Testing (PIXIT).

6.1.1 Embedded MAUs

Many of these tests do not apply to embedded MAUs where the physical AUI does not exist. In those cases, other standards may apply.

6.2 10BASE-T MAU abstract test suite

This is comprised of one category of test groups. The category relates to capability testing. Within this category are a number of test groups, where each group is aimed at collecting individual test cases together that share some commonality in features tested or test methods used. The MAU test method is Local Single as per ISO/IEC 9646. The format for the test case headers follows the outline of 1.5, with the addition of a PICS Reference: line that cross-references the test case to a particular PICS subclause/item of ISO/IEC 8802-3 [IEEE Std 802.3].

Test Suite ID	:	1411
Test Suite Name	:	10BASE-T MAU Abstract Tests
Applicable Standards	:	ISO/IEC 8802-3
OSI RM Layer	:	Physical
OSI RM Sublayer	:	Medium Attachment Unit (MAU)
Class or Access	:	CSMA/CD
Transmission Type	:	10BASE-T
Purpose	:	To assess conformance of the physical interface to applicable standards.
General Setup	:	Unless otherwise stated in individual test procedures, all tests shall start
		with Apply power to the MAU and bring the MAU into Link Test Pass
		State. In addition, all tests requiring the application of power to the
		MAU via the AUI shall be performed with 11.28 V applied through a
		$3.5 \ \Omega \ 1\%$ resistor to the VP circuit of the MAU and with 15.75 V applied
		through no series resistor to the VP circuit of the MAU, unless otherwise
		stated. For both voltage levels, all stray wiring and connection resistance
		for both the VP circuit and the VC circuit combined shall be limited to a
		maximum of 0.405 Ω excluding the resistance of conformant AUI con-
		nector connections at the source and MAU ends. All AUI applied

voltages are with reference to circuit VC. When required, the MAU can be verified to be in a Link Test Fail state by monitoring the DI circuit for input_idle messages and the TD circuit for TD_idle messages.

6.2.1 Capability and behavior tests

6.2.1.1 Test group 1411.01 — transmit functions

Test Group Name : Transmit functions. Test Group Purpose : To verify the characteristics of the Transmit function. Test Case ID : 1411.01.01 Test Case Name : Transmit signal polarity. Status MANDATORY Standard Reference : 14.10.4.5.2/1, 14.10.4.5.2/2 History : : Test Servere : 14.10.4.5.2/1, 14.10.4.5.2/2 Note : : Test Purpose : To verify the polarity of the TD circuit signals in relation to the DO circuit signals. Note : : : Test Setup : Test setup B. : Test Procedure : Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and the TD circuit of the MDI. A positive signal on the A lead relative to the B lead of the DO circuit shall result in a positive signal on the TD- (Transmit Data +) lead of the MDI with respect to the TD- lead. Test Case ID : 1411.01.02 Test Case Name : Transmit start-up bit loss. Status : MANDATORY Status : MANDATORY Status : To	Test Group ID	: 1411.01
Test Case ID : 1411.01.01 Test Case Name : Transmit signal polarity. Status : MANDATORY Standard Reference : 14.2.1.1 PICS Reference : 14.1.0.4.5.2/1, 14.10.4.5.2/2 History : : Test Steppee : To verify the polarity of the TD circuit signals in relation to the DO circuit signals. Note : : : Test Setup : Test setup B. : Test Procedure : Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and the TD circuit for correct logical sense after the initial bit-loss time and before the start of idle of a packet transmission. Conformance : The MAU shall receive the signals on the DO circuit and send them to the TD circuit of the MDI. A positive signal on the 1 Lead relative to the B lead of the DO circuit shall result in a positive signal on the TD+ (Transmit Data +) lead of the MDI with respect to the TD- lead. Test Case ID : 1411.01.02 Test Case Name : Transmit start-up bit loss. Status : MANDATORY Status : MANDATORY Status : MANDATORY <td< th=""><th>Test Group Name</th><th>: Transmit functions.</th></td<>	Test Group Name	: Transmit functions.
Test Case Name : Transmit signal polarity. Status : MANDATORY Standard Reference : 14.2.1.1 PICS Reference : 14.1.0.4.5.2/1, 14.10.4.5.2/2 History : : Test Purpose : To verify the polarity of the TD circuit signals in relation to the DO circuit signals. Note : : : Test Setup : Test setup B. : Test Procedure : Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and the TD circuit of the MDI colority and send them to the TD circuit of the MDI. A positive signal on the A lead relative to the B lead of the DO circuit shall result in a positive signal on the TD+ (Transmit Data +) lead of the MDI with respect to the TD- lead. Test Case ID : 1411.01.02 Test Case Name : Transmit start-up bit loss. Status : MANDATORY Standard Reference : 14.2.1.1 PICS Reference	Test Group Purpose	: To verify the characteristics of the Transmit function.
Status : MANDATORY Standard Reference : 14.2.1.1 PICS Reference : 14.10.4.5.2/1, 14.10.4.5.2/2 History : : Test Purpose : To verify the polarity of the TD circuit signals in relation to the DO circuit signals. Note : : Test Setup : Test setup B. Test Procedure : Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and the TD circuit for correct logical sense after the initial bit-loss time and before the start of idle of a packet transmission. Conformance : The MAU shall receive the signals on the DO circuit and send them to the TD circuit of the MDI. A positive signal on the TD+ (Transmit Data +) lead of the DO circuit shall result in a positive signal on the TD+ (Transmit Data +) lead of the MDI with respect to the TD- lead. Test Case ID : 1411.01.02 Test Case Name : Transmit start-up bit loss. Status : MANDATORY Standard Reference : 14.2.1.1 PICS Reference : 14.10.4.5.2/3 History : : Test Case Name : To verify the number of bits received on the DO circuit and not transmitted on the TD ci	Test Case ID	: 1411.01.01
Standard Reference : 14.10.4.5.2/1, 14.10.4.5.2/2 History : : Test Purpose : To verify the polarity of the TD circuit signals in relation to the DO circuit signals. Note : : Test Setup : Test setup B. Test Procedure : Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and the TD circuit for correct logical sense after the initial bit-loss time and before the start of idle of a packet transmission. Conformance : The MAU shall receive the signals on the DO circuit and send them to the TD circuit of the MDI. A positive signal on the A lead relative to the B lead of the DO circuit shall result in a positive signal on the TD+ (Transmit Data +) lead of the MDI with respect to the TD- lead. Test Case ID : 1411.01.02 Test Case Name : Transmit start-up bit loss. Status : MANDATORY Status : 141.0.4.5.2/3 History : : Test Setup : Test setup B. Test Purpose : <t< td=""><td>Test Case Name</td><td>: Transmit signal polarity.</td></t<>	Test Case Name	: Transmit signal polarity.
PICS Reference : 14.10.4.5.2/1, 14.10.4.5.2/2 History : . Test Purpose : To verify the polarity of the TD circuit signals in relation to the DO circuit signals. Note : : Test Setup : Test setup B. Test Procedure : Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and the TD circuit for correct logical sense after the initial bit-loss time and before the start of idle of a packet transmission. Conformance : The MAU shall receive the signals on the DO circuit and send them to the TD circuit of the MDI. A positive signal on the TD+ (Transmit Data +) lead of the DO circuit shall result in a positive signal on the TD- (Transmit Data +) lead of the MDI with respect to the TD- lead. Test Case ID : 1411.01.02 Test Case Name : Transmit start-up bit loss. Status : MANDATORY Standard Reference : 14.10.4.5.2/3 History : : Test Setup : Test setup B. Test Purpose : To verify the number of bits received on the DO circuit and not transmitted on the TD circuit. Note : : : Test Setup : Test	Status	: MANDATORY
History : Test Purpose : To verify the polarity of the TD circuit signals in relation to the DO circuit signals. Note : Test Setup : Test Setup : Test Procedure : Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and the TD circuit for correct logical sense after the initial bit-loss time and before the start of idle of a packet transmission. Conformance : The MAU shall receive the signals on the DO circuit and send them to the TD circuit of the MDI. A positive signal on the A lead relative to the B lead of the DO circuit shall result in a positive signal on the TD+ (Transmit Data +) lead of the MDI with respect to the TD- lead. Test Case ID : 1411.01.02 Test Case Name : Transmit start-up bit loss. Status : MANDATORY Standard Reference : 14.10.4.5.2/3 History : : Test Setup : Test setup B. Test Purpose : Test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and not transmitted on the TD circuit. Note : : : Test Purpose : Test setup B.	Standard Reference	: 14.2.1.1
History : Test Purpose : To verify the polarity of the TD circuit signals in relation to the DO circuit signals. Note : Test Setup : Test Setup : Test Procedure : Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and the TD circuit for correct logical sense after the initial bit-loss time and before the start of idle of a packet transmission. Conformance : The MAU shall receive the signals on the DO circuit and send them to the TD circuit of the MDI. A positive signal on the A lead relative to the B lead of the DO circuit shall result in a positive signal on the TD+ (Transmit Data +) lead of the MDI with respect to the TD- lead. Test Case ID : 1411.01.02 Test Case Name : Transmit start-up bit loss. Status : MANDATORY Standard Reference : 14.10.4.5.2/3 History : : Test Setup : Test setup B. Test Purpose : Test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and not transmitted on the TD circuit. Note : : : Test Purpose : Test setup B.	PICS Reference	: 14.10.4.5.2/1, 14.10.4.5.2/2
Test Purpose : To verify the polarity of the TD circuit signals in relation to the DO circuit signals. Note : Test Setup : Test setup B. Test Procedure : Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and the TD circuit for correct logical sense after the initial bit-loss time and before the start of idle of a packet transmission. Conformance : The MAU shall receive the signals on the DO circuit and send them to the TD circuit of the MDI. A positive signal on the A lead relative to the B lead of the DO circuit shall result in a positive signal on the TD+ (Transmit Data +) lead of the MDI with respect to the TD- lead. Test Case ID : 1411.01.02 Test Case Name : To verify the number of bits received on the DO circuit and not transmitted on the TD circuit. Vistory : : Test Setup : To verify the number of bits received on the DO circuit and not transmitted on the TD circuit. Note : : To verify the number of bits received on the DO circuit and not transmitted and tD circuit. Note : : Test setup B. : Test Purpose : Test setup B. : Test setup D circuit. Test Procedure : Apply test signal 1 to the DO circuit and not transm		:
Note : Test Setup : Test setup B. Test Procedure : Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and the TD circuit for correct logical sense after the initial bit-loss time and before the start of idle of a packet transmission. Conformance : The MAU shall receive the signals on the DO circuit and send them to the TD circuit of the MDI. A positive signal on the A lead relative to the B lead of the DO circuit shall result in a positive signal on the TD+ (Transmit Data +) lead of the MDI with respect to the TD- lead. Test Case ID : 1411.01.02 Test Case Name : Transmit start-up bit loss. Status : MANDATORY Standard Reference : 14.1.04.5.2/3 History : : Test Setup : Test setup B. Test Purpose : Test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and not transmitted on the TD circuit. Note : : : Test Procedure : Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and not transmitted on the TD circuit. Note : : : Test Setup : Test setup B. Test Procedure <td< td=""><td>•</td><td></td></td<>	•	
Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and the TD circuit for correct logical sense after the initial bit-loss time and before the start of idle of a packet transmission.Conformance:The MAU shall receive the signals on the DO circuit and send them to the TD circuit of the MDI. A positive signal on the A lead relative to the B lead of the DO circuit shall result in a positive signal on the TD+ (Transmit Data +) lead of the MDI with respect to the TD- lead.Test Case ID:1411.01.02Test Case Name:Transmit start-up bit loss.Status:MANDATORYStandard Reference:14.2.1.1PICS Reference:14.1.0.4.5.2/3History:Test Purpose:To verify the number of bits received on the DO circuit and not transmit- ted on the TD circuit.Note:Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and not transmit- ted on the TD circuit.Note:Test Purpose:Test setup B.Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter (SFD) for reference.Conformance::At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmited on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid amplitude.Test Case ID:1411.01.03	Note	:
Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and the TD circuit for correct logical sense after the initial bit-loss time and before the start of idle of a packet transmission.Conformance:The MAU shall receive the signals on the DO circuit and send them to the TD circuit of the MDI. A positive signal on the A lead relative to the B lead of the DO circuit shall result in a positive signal on the TD+ (Transmit Data +) lead of the MDI with respect to the TD- lead.Test Case ID:1411.01.02Test Case Name:Transmit start-up bit loss.Status:MANDATORYStandard Reference:14.2.1.1PICS Reference:14.1.0.4.5.2/3History:Test Purpose:To verify the number of bits received on the DO circuit and not transmit- ted on the TD circuit.Note:Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and not transmit- ted on the TD circuit.Note:Test Purpose:Test setup B.Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter (SFD) for reference.Conformance::At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmited on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid amplitude.Test Case ID:1411.01.03	Test Setup	: Test setup B.
the TD circuit of the MDI. A positive signal on the A lead relative to the B lead of the DO circuit shall result in a positive signal on the TD+ (Transmit Data +) lead of the MDI with respect to the TD- lead.Test Case ID:1411.01.02Test Case Name:Transmit start-up bit loss.Status:MANDATORYStandard Reference:14.2.1.1PICS Reference:14.10.4.5.2/3History:Test Setup:To verify the number of bits received on the DO circuit and not transmitted on the TD circuit.Note:Test Setup:Test setup B.Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter (SFD) for reference.Conformance:At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmitted on the TD circuit.Test Case ID:1411.01.03		: Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and the TD circuit for correct logical sense after the initial bit-loss time
Test Case Name:Transmit start-up bit loss.Status:MANDATORYStandard Reference:14.2.1.1PICS Reference:14.10.4.5.2/3History:Test Purpose:To verify the number of bits received on the DO circuit and not transmit- ted on the TD circuit.Note:Test Setup:Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Measure the number of bits received on the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter (SFD) for reference.Conformance:At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmitted on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid amplitude.Test Case ID:1411.01.03	Conformance	the TD circuit of the MDI. A positive signal on the A lead relative to the B lead of the DO circuit shall result in a positive signal on the TD+
Status:MANDATORYStandard Reference:14.2.1.1PICS Reference:14.10.4.5.2/3History:Test Purpose:To verify the number of bits received on the DO circuit and not transmit- ted on the TD circuit.Note:Test Setup:Test setup B.Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Measure the number of bits received on the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter (SFD) for reference.Conformance:At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmitted on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid amplitude.Test Case ID:1411.01.03	Test Case ID	: 1411.01.02
Status:MANDATORYStandard Reference:14.2.1.1PICS Reference:14.10.4.5.2/3History:Test Purpose:To verify the number of bits received on the DO circuit and not transmit- ted on the TD circuit.Note:Test Setup:Test setup B.Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Measure the number of bits received on the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter (SFD) for reference.Conformance:At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmitted on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid amplitude.Test Case ID:1411.01.03	Test Case Name	: Transmit start-up bit loss.
PICS Reference:14.10.4.5.2/3History:Test Purpose:To verify the number of bits received on the DO circuit and not transmit- ted on the TD circuit.Note:Test Setup:Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Measure the number of bits received on the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter (SFD) for reference.Conformance:At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmitted on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid amplitude.Test Case ID:1411.01.03	Status	
History:Test Purpose:To verify the number of bits received on the DO circuit and not transmitted on the TD circuit.Note:Test Setup:Test setup B.Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Measure the number of bits received on the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter (SFD) for reference.Conformance:At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmitted on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid amplitude.Test Case ID:1411.01.03	Standard Reference	: 14.2.1.1
History:Test Purpose:To verify the number of bits received on the DO circuit and not transmitted on the TD circuit.Note:Test Setup:Test setup B.Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Measure the number of bits received on the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter (SFD) for reference.Conformance:At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmitted on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid amplitude.Test Case ID:1411.01.03	PICS Reference	: 14.10.4.5.2/3
Test Purpose:To verify the number of bits received on the DO circuit and not transmitted on the TD circuit.Note:Test Setup:Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Measure the number of bits received on the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter (SFD) for reference.Conformance:At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmitted on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid amplitude.Test Case ID:1411.01.03		:
Test Setup:Test setup B.Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Measure the number of bits received on the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter (SFD) for reference.Conformance:At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmitted on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid amplitude.Test Case ID:1411.01.03		
Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Measure the number of bits received on the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter (SFD) for reference.Conformance:At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmitted on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid amplitude.Test Case ID:1411.01.03	Note	:
Test Procedure:Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Measure the number of bits received on the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter (SFD) for reference.Conformance:At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmitted on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid amplitude.Test Case ID:1411.01.03		: Test setup B.
by the MAU from the DO circuit and not transmitted on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid amplitude. Test Case ID : 1411.01.03	-	: Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Measure the number of bits received on the DO circuit and not transmitted onto the TD circuit using the Start Frame Delimiter
	Conformance	: At the start of a packet transmission, no more than 2 bits may be received by the MAU from the DO circuit and not transmitted on the TD circuit. It is permissible for the first bit sent to contain phase violations or invalid
	Test Case ID	: 1411.01.03

Status Standard Reference PICS Reference History Test Purpose Note Test Setup Test Procedure	 MANDATORY 14.2.1.1 14.10.4.5.2/4 To verify the timing and signal level of the second bit cell transmitted. Test setup B. Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Observe the second and subsequent bits on the TD circuit
Conformance	 circuit. The second bit transmitted on the TD circuit shall be transmitted with the correct timing and signal levels.
Test Case ID	: 1411.01.04
Test Case Name	: Transmit steady-state delay.
Status	: MANDATORY
Standard Reference	: 14.2.1.1
PICS Reference	: 14.10.4.5.2/5
History	
Test Purpose	To verify the propagation delay between the DO circuit and the TD
rest r urpose	circuit.
Note	·
Test Setup	: Test setup B.
Test Procedure	: Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit
	and TD circuit. Measure the propagation delay from a bit s zero crossing on the DO circuit to the corresponding bit s zero crossing on the TD cir- cuit using the SFD for reference.
Conformance	: The steady-state propagation delay between the DO circuit input and the TD circuit shall not exceed 2 bit times.
Test Case ID	: 1411.01.05
Test Case Name	: Transmit delay variability.
Status	: MANDATORY.
Standard Reference	: 14.2.1.1
PICS Reference	: 14.10.4.5.2/6
History	:
Test Purpose	: To verify the start-up delay variability between two packets.
Note	:
Test Setup	: Test setup B.
Test Procedure	: Apply test signals 2a–f to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Measure the start-up delay (bit loss plus steady-state propagation delay) for a packet and the subsequent packet. Repeat the test 100 times to determine the largest variability.
Conformance	: For any two packets that are separated by 9.6 µs or less, the start-up delay (bit loss plus steady-state propagation delay) of the first packet shall not exceed that of the second packet by more than 2 bit times.
Test Case ID	: 1411.01.06
Test Case Name	: TP_IDL, silence duration and silence voltage.
Status	: MANDATORY
Standard Reference	: 14.2.1.1
PICS Reference	: 14.10.4.5.2/7, 14.10.4.5.2/8

History	:
Test Purpose	: To verify the timing of the TP_IDL signal.
Note	
Test Setup	: Test setup B.
Test Procedure	 Apply test signal 1 to the DO circuit of the MAU. Monitor the TD circuit Measure the period of silence between the start of TP_IDL and the lir test pulse. Measure the time between repeating link test pulses.
Conformance	: Whenever data is not being transmitted on the TD circuit, an idle signal TP_IDL, shall be transmitted on the TD circuit. TP_IDL is a start of id as defined in 14.3.1.2.1 followed by a repeating sequence of a 16 n \pm 8 ms period of silence (the time where the differential voltage remain at 0 mV \pm 50 mV) and a link test pulse (see 14.3.1.2.1).
Test Case ID	: 1411.01.07
Test Case Name	: TP_IDL signal termination with respect to start of packet and link te pulse.
Status	: MANDATORY
Standard Reference	: 14.2.1.1
PICS Reference	: 14.10.4.5.2/9
History	:
Test Purpose	: To verify correct termination of the TP_IDL signal.
Note	: This test case is considered untestable. It is not practical to measure an
	is not considered critical. Even though testing for compliance is not pra tical, conformance to the standard, by design, is the responsibility of the
Tart Catao	manufacturer with compliance status to be noted in the PICS.
Test Setup Test Procedure	
Conformance	: Terescondering of TD IDI many he to main stad of our time with some st
Conformatice	: Transmission of TP_IDL may be terminated at any time with respect the link test pulse. It shall be terminated such that no more than the fir transmitted bit of a packet is corrupted and with no more delay than specified for bit loss and steady-state propagation.
2.1.2 Test group 141	1.02 — receive functions
Test Group ID	: 1411.02
Test Group Name	: Receive Functions.
Test Group Purpose	: To verify the characteristics of the Receive Function.
Test Case ID	: 1411.02.01
Test Case Name	: Receive start-up bit loss.
Status	: MANDATORY
Standard Reference	: 14.2.1.2
PICS Reference	: 14.10.4.5.3/3
History	:
Test Purpose	: To verify the number of bits received on the RD circuit and not transmitted on the DI circuit.
Note	:
Test Setup	: Test setup L.
Test Procedure	: Apply test signal 1 to the DO circuit of the tester MAU. Monitor the R circuit and DI circuit on the MAU under test. Measure the number of bir received on the RD circuit of the MAU under test and not transmitted of test and
Conformance	the DI circuit of the MAU under test using the SFD for reference.At the start of a packet reception from the RD circuit, no more than 5 bit

Test Case ID	: 1411.02.02
Test Case Name	: Receive steady-state delay.
Status	: MANDATORY
Standard Reference	14.2.1.2
PICS Reference	: 14.10.4.5.3/5
History	:
Test Purpose	: To verify the propagation delay from the RD circuit to the DI circuit.
Note	:
Test Setup	: Test setup L.
Test Procedure	: Apply test signal 1 to the DO circuit of the tester MAU. Monitor the DI circuit and RD circuit on the MAU under test. Measure the propagation delay between a bit s zero crossing on the RD circuit of the MAU under test and the corresponding bit s zero crossing on the DI circuit of the MAU under test using the SFD for reference.
Conformance	: The steady-state propagation delay between the RD circuit and the DI circuit shall not exceed 2 bit times.
Test Case ID	: 1411.02.03
Test Case Name	: Receive signal polarity.
Status	: MANDATORY
Standard Reference	: 14.2.1.2
PICS Reference	: 14.10.4.5.3/1, 14.10.4.5.3/2
History	:
Test Purpose	: To verify the polarity of the DI circuit signals in relation to the RD circuit signals.
Note	:
Test setup	: Test setup L
Test Procedure	: Apply test signal 1 to the DO circuit of the tester MAU. Monitor the DI circuit and RD circuit signals on the MAU under test for correct logical sense after the initial bit-loss time and before the start of idle of the packet.
Conformance	: The MAU shall receive the signals on the RD circuit of the MDI and send them to the DI circuit. A positive signal on the RD+ (Receive Data +) lead relative to the RD– lead of the MDI shall result in a positive signal on the A lead with respect to the B lead of the DI circuit.
Test Case ID	: 1411.02.04
Test Case Name	: Receive delay variability.
Status	: MANDATORY
Standard Reference	: 14.2.1.2
PICS Reference	: 14.10.4.5.3/6
History	:
Test Purpose	: To verify the start-up delay between two packets.
Note	
Test Setup	: Test setup H.
Test Procedure	: Apply test signals 24a—f to the RD circuit of the MAU under test. Mon- itor the DI circuit and RD circuit signals. Measure how much the start-up delay (bit loss plus steady-state propagation delay) exceeds the delay of the subsequent packet. Repeat the test 100 times and note the worst-case

may be received from the RD circuit and not transmitted onto the DI circuit.

Conformance	:	value. For any two packets that are separated by 9.6 s or less, the start-up delay (bit loss plus steady-state propagation delay) of the first packet shall not exceed that of the second packet by more than 2 bit times.
Test Case ID	:	1411.02.05
Test Case Name	:	Receive settling time.
Status	:	MANDATORY
Standard Reference	:	14.2.1.2
PICS Reference	:	14.10.4.5.3/4
History	:	
Test Purpose	:	To verify the timing and signal level of the second bit transmitted.
Note	:	
Test Setup	:	Test setup L.
Test Procedure	:	Apply test signal 1 to the DO circuit of the tester MAU. Monitor the D circuit and RD circuit on the MAU under test. Observe the second and subsequent bits on the DI circuit of the MAU under test.
Conformance	:	It is permissible for the first bit sent on the DI circuit to contain phase violations or invalid data; however all successive bits of the packet shal be sent with no more than the amount of jitter specified in 14.3.1.3.1.
2.1.3 Test group 1411	1.03 –	– loopback functions
Test Group ID	:	1411.03
Test Group Name	:	Loopback functions.
Test Group Purpose	:	To verify the functional characteristics of the Loopback function.
Test Case ID	:	1411.03.01
Test Case Name	:	Loopback function when $RD = idle$ and $DO = active$.
Status	:	MANDATORY
Standard Reference	:	14.2.1.3
PICS Reference	:	14.10.4.5.4/1
History	:	
Test Purpose	:	To verify the loopback function requirements when RD is idle and DO i active.
Note	:	
Test Setup	:	Test setup B.
Test Procedure	:	Apply test signal 1 to the DO circuit of the MAU. Monitor the DI circuit
Conformance	:	When the MAU is transmitting on the TD circuit and is not receiving
		RD_input messages on the RD circuit, the MAU shall transmit on the D
		circuit the signals received on the DO circuit in order to provide loopbac of the transmitted signal.
Test Case ID	:	1411.03.02
Test Case Name	•	Loopback bit loss (DO to DI circuits).
Status	:	MANDATORY
Standard Reference	:	14.2.1.3
PICS Reference	:	14.2.1.5 14.10.4.5.4/2
History	:	17,10,7,3,7/2
Test Purpose	:	To verify the number of bits transmitted on the DO circuit and not re
rest i uipose	•	ceived on the DI circuit.

Note Test Setup Test Procedure Conformance	 : Test setup B. : Apply test signal 1 to the DO circuit of the MAU. Monitor the DI circuit and DO circuit. Measure the number of bits received on the DO circuit and not transmitted on the DI circuit using the SFD for reference. : At the start of a packet transmission on the TD circuit, no more than 5 bits of information may be received from the DO circuit and not transmitted to the DI circuit.
Test Case ID	: 1411.03.03
Test Case Name	: Loopback steady-state delay.
Status	: MANDATORY
Standard Reference	: 14.2.1.3
PICS Reference	: 14.10.4.5.4/4
History	:
Test Purpose	: To verify the propagation delay from the DO circuit to the DI circuit.
Note	:
Test Setup	: Test setup B.
Test Procedure	: Apply test signal 1 to the DO circuit of the MAU. Monitor the DI circuit and DO circuit. Measure the propagation delay from a bit s zero crossing on the DO circuit to the corresponding bit s zero crossing on the DI cir- cuit using the SFD for reference.
Conformance	: The steady-state propagation delay between the DO circuit and the DI circuit shall not exceed 1 BT.
Test Case ID	: 1411.03.04
Test Case Name	: Loopback settling time.
Status	: MANDATORY
Standard Reference	: 14.2.1.3
PICS Reference	: 14.10.4.5.4/3
History	:
Test Purpose	: To verify the timing and signal level of the second bit cell transmitted.
Note	:
Test Setup	: Test setup B.
Test Procedure	 Apply test signal 1 to the DO circuit of the MAU. Monitor the DI circuit and DO circuit signals. Observe the second and subsequent bits of the DI circuit data.
Conformance	: It is permissible for the first bit sent on the DI circuit to contain phase violations or invalid data; however, all successive bits of the packet shall meet the jitter specified in 14.3.1.3.1 (that is, 13.5 ns + 1.5 ns).

	1411.04
Test Group ID	: 1411.04
Test Group Name	: Collision functions.
Test Group Purpose	: To verify the functional characteristics of the collision function.
Test Case ID	: 1411.04.01
Test Case Name	: No collision state.
Status	: MANDATORY
Standard Reference	: 14.2.1.4
PICS Reference	: 14.10.4.5.5/4
History	:
Test Purpose	: To verify the presence and the signal characteristics of IDL on the CI cir cuit when there is no collision, SQE test, or jabber.
Note	:
Test Setup	: Test setup M.
Test Procedure	: Monitor the CI circuit of the MAU under test.
	(1) Apply test signal 1 to the DO circuit of the tester MAU and IDI
	to the DO circuit of the MAU under test.
	(2) Apply test signal 1 to the DO circuit of the MAU under test and
	IDL to the DO circuit of the tester MAU.
	Verify that CI is asserting IDL while DI is active.
Conformance	: The signal present on the CI circuit in the absence of a collision, SQI
Comoniance	test, or jabber shall be the IDL signal.
Test Case ID	: 1411.04.02
Test Case Name	Collision state.
Status	: MANDATORY
Standard Reference	: 14.2.1.4
PICS Reference	: 14.2.1.4 : 14.10.4.5.5/1
History	. 14.10.4.5.5/1
Test Purpose	: To verify the presence and the signal characteristics of CS0 on the CI cir
rest ruipose	cuit when there is a collision.
Mata	cuit when there is a comsion.
Note Test Set	: The stand of O
Test Setup	: Test setup O.
Test Procedure	 Monitor the CI circuit, DO circuit, and TD circuit of the MAU under test (1) Apply test signal 1 to the DO circuit of the tester MAU. Apply test signal 1 to the DO circuit of the MAU under test to create collision. Verify on the MAU under test that the signals on th DO circuit appear on the TD circuit and that CS0 is present of the CI circuit (see Figure 6-1a).
	(2) Apply test signal 1 to the DO circuit of the MAU under test. Apply test signal 1 to the DO circuit of the tester MAU to create collision. Verify on the MAU under test that the signals on th DO circuit appear on the TD circuit and that CS0 is present of the CI circuit (see Figure 6-1b).
Conformance	: While a collision is detected, a CS0 signal [see 7.3.1.2 of ISO/IE0 8802-3 (IEEE Std 802.3)] shall be sent on the CI circuit.
Test Case ID	: 1411.04.03
Test Case Name	: Collision indication delay.

6.2.1.4 Test group 1411.04 — collision functions

Status	: MANDATORY
Standard Reference	: 14.2.1.4
PICS Reference	: 14.10.4.5.5/2
History	:
Test Purpose	: To verify the delay between the collision start and the collision present state indicated on CI circuit.
Note	:
Test Setup	: Test setup O.
Test Procedure	 Monitor the CI circuit, DO circuit, and RD circuit of the MAU under test Apply test signal 1 to the DO circuit of the tester MAU. App test signal 1 to the DO circuit of the MAU under test to create collision. Measure the delay from collision start (application of the second test signal on the DO circuit of the MAU under test to commencement of the CS0 signal on the CI circuit (se Figure 6-1a). Apply test signal 1 to the DO circuit of the tester MAU under test a collision. Measure the delay from collision start (applander test of the second test signal 1 to the DO circuit of the MAU under test a collision. Measure the delay from collision start (appearance of the second test signal 1 to the DO circuit of the tester MAU to create a collision. Measure the delay from collision start (appearance of the second test signal on the RD circuit of the MAU under test) to commencement of the CS0 signal on the CI circuit (see Figure 6-1b).
Conformance	: The CS0 signal shall be presented to the CI circuit no more than 9 times after the occurrence of a collision.
Test Case ID	: 1411.04.04
Test Case Name	: Collision indication deassert delay.
Status	: MANDATORY
Standard Reference	: 14.2.1.4
PICS Reference	: 14.10.4.5.5/3
History	
Test Purpose	: To verify the cessation of the CS0 signal after the collision condition removed

rcuit, DO circuit, and RI
r

/Ionitor	the CI circuit, DO circuit, and RD circuit of the MAU under test.
(1)	Apply test signal 1 to the DO circuit of the tester MAU. Apply
	test signal 1 to the DO circuit of the MAU under test to create a
	collision. Monitor the CI circuit for the presence of the CS0 sig-
	nal. Stop the application of the test signal on the DO circuit of
	the tester MAU. Measure the time from the last transition of the
	test signal on the RD circuit of the MAU under test until the
	CS0 signal on the CI circuit stops (see Figure 6-1a).

(2) Apply test signal 1 to the DO circuit of the MAU under test. Apply test signal 1 to the DO circuit of the tester MAU to create a collision. Monitor the CI circuit for the presence of the CS0 signal. Stop the application of the test signal on the DO circuit of the MAU under test. Measure the time from the last transition of the test signal on the DO circuit of the CS0 signal on the DO circuit stops (see Figure 6-1b).
: The CS0 signal on the CI circuit shall be deasserted within 9 bit times

Conformance

The CS0 signal on the CI circuit shall be deasserted within 9 bit times after the DO circuit or the RD circuit changes from active to idle.

IEEE

Std 1802.3-2001



a) Test signal applied to tester MAU, then MAU under test



b) Test signal applied to MAU under test, then tester MAU



Test Case ID	: 1411.04.05
Test Case Name	: DI circuit source switch delay from CS0 assert.
Status	: MANDATORY
Standard Reference	: 14.2.1.4
PICS Reference	: 14.10.4.5.5/5
History	:
Test Purpose	: To verify the delay between the start of collision and the presence of RD data on the DI circuit.
Note	:
Test Setup	: Test setup M.
Test Procedure	: Apply test signal 19a to the DO circuit of the MAU under test. Monitor the CI circuit and DI circuit of the MAU under test. Apply test signal 19b to the DO circuit of the tester MAU at least 65 BT after the test signal on the MAU under test is applied to create a collision. Monitor the CI circuit for the presence of the CS0 signal. Measure the delay between the asser- tion of CS0 and commencement of input on the DI circuit corresponding to the test signal applied to the tester MAU. The signals applied to the DO circuit of the tester MAU and the DO circuit of the MAU under test are different to facilitate differentiation between DO loopback and RD.
Conformance	: When CS0 is asserted on the CI circuit due to a collision, the data on the RD circuit shall be sent to the DI circuit within 9 bit times.
Test Case ID	: 1411.04.06
Test Case Name	: DI circuit source switch delay from CS0 deassert.
Status	: MANDATORY
Standard Reference	: 14.2.1.4
PICS Reference	: 14.10.4.5.5/6
History	:
Test Purpose	: To verify the delay between the end of collision and the presence of DO data on the DI circuit.
Note	:
Test Setup	: Test setup M.
Test Procedure	 Apply the test signal 19a to the DO circuit of the MAU under test. Monitor the CI circuit, RD circuit and DI circuit of the MAU under test. Apply test signal 19b to the DO circuit of the tester MAU at least 65 BT after the test signal on the MAU under test is applied to create a collision. Monitor the CI circuit for the presence of the CS0 signal. After CS0 is asserted, stop transmitting on the DO circuit (14.2.2.5) and the presence of the DO circuit of the tester MAU. Measure the delay between idle on the RD circuit. The signals applied to the DO circuit of the tester mAU and the DO circuit of the MAU under test are different to facilitate differentiation between RD circuit data and DO loopback.
Conformance	: When the RD circuit changes from active to idle and data is present on the DO circuit, the data on the DO circuit shall be sent to the DI circuit within 9 bit times.

6.2

Test Group ID	:	1411.05
Test Group Name	:	Signal_quality_error Message (SQE) Test functions.
Test Group Purpose	:	To verify the functional characteristics of the SQE test functions.

Test Case ID Test Case Name Status	 1411.05.01 SQE_test_timer range. CONDITIONAL (SQE Test function shall be performed by MAUs connected to DTEs and shall not be performed for MAUs connected to repeaters).
Standard Reference PICS Reference History	: 14.2.1.5 : 14.10.4.5.6/3, 14.10.4.5.6/4 :
Test Purpose Note	 To verify the duration of the SQE Test state after the end of a frame transmission. Duration of CS0 is between first excursion outside 0 mV ± 40 mV and the last positive transition.
Test Setup	: Test setup B.
Test Procedure	 Apply test signal 1 to the DO circuit of the MAU. Monitor the CI circuit. Measure duration of the CS0 signal on the CI circuit.
Conformance	: The MAU shall send CS0 on the CI circuit for a time SQE_test begin- ning a time SQE_test_wait after the last positive transition on the DO circuit. The value of SQE_test shall be 10 bit ± 5 bit times.
Test Case ID	: 1411.05.02
Test Case Name	: SQE_test_wait_timer range.
Status	: CONDITIONAL (SQE Test function shall be performed by MAUs
Status	connected to DTEs and shall not be performed for MAUs connected to repeaters).
Standard Reference	: 14.2.1.5
PICS Reference	: 14.10.4.5.6/2
History	
Test Purpose	 To verify the duration of the SQE Test Wait state after the end of a frame transmission.
Note	: Duration of CS0 is between first excursion outside $0 \text{ mV} \pm 40 \text{ mV}$ and the last positive transition.
Test Setup	: Test setup B.
Test Procedure	: Apply test signal 1 to the DO circuit of the MAU. Monitor the DO circuit and CI circuit. Measure time delay between the last positive transition of the data on the DO circuit and the assertion of CS0 on the CI circuit.
Conformance	: The MAU shall send CS0 on the CI circuit beginning a time SQE_test_wait after the last positive transition of a packet on the DO circuit. The value of SQE_test_wait shall be between 0.6 μs and 1.6 μs.
Test Case ID	: 1411.05.03
Test Case Name	: SQE Test function interference.
Status	: CONDITIONAL (SQE Test function shall be performed by MAUs connected to DTEs and shall not be performed for MAUs connected to repeaters).
Standard Reference	: 14.2.1.5
PICS Reference	: 14.10.4.5.6/1
History	:
Test Purpose	: To verify the effect of the SQE Test function on the TD and DI circuits.
Note	: Extraneous signal on the TD circuit is defined to be greater than $\pm 50 \text{ mV}$; extraneous signal on the DI circuit is defined to be greater than $\pm 40 \text{ mV}$.
Test Setup	: Test setup B.

	IEEE CONFORMANCE TEST METHODOLOGY FOR IEEE STANDARDS FOR LAN MAN
Test Procedure	: Apply test signal 1 to the DO circuit of the MAU. Monitor the DI circuit and TD circuit for 3 µs after the end of frame transmission.
Conformance	: This function should not introduce extraneous signals on the TD circor or the DI circuit.
Test Case ID	: 1411.05.04
Test Case Name	: SQE Test function in link fail state.
Status	: CONDITIONAL (SQE Test function shall be performed by MA connected to DTEs and shall not be performed for MAUs connected repeaters).
Standard Reference	: 14.2.1.5
PICS Reference	: 14.10.4.5.6/5
History	:
Test Purpose	: To verify that the SQE Test function does not transmit a CS0 signal wh MAU is in a Link Test Fail state.
Note	:
Test Setup	: Test setup N.
Test Procedure	: Apply power to the MAU under test. Monitor the AUI CI circuit of MAU under test. Wait for 151 ms then apply test signal 1 to the DO cuit of the MAU under test. Check that the MAU is in a Link Test F state. Verify that CS0 is not asserted on the CI circuit for at least 3.1
Conformance	: The CS0 signal shall not be sent by the SQE Test function while in a of the Link Test Fail states.
Test Group ID Test Group Name Test Group Purpose	 1411.06 Jabber functions. To verify the functional characteristics of the jabber functions.
Test Case ID	. 1411.06.01
Test Case ID Test Case Name	: 1411.06.01 Xmit max timer range
Test Case Name	: Xmit_max_timer range.
	Xmit_max_timer range.MANDATORY
Test Case Name Status	 Xmit_max_timer range. MANDATORY 14.2.1.6
Test Case Name Status Standard Reference	Xmit_max_timer range.MANDATORY
Test Case Name Status Standard Reference PICS Reference	 Xmit_max_timer range. MANDATORY 14.2.1.6
Test Case Name Status Standard Reference PICS Reference History	 Xmit_max_timer range. MANDATORY 14.2.1.6 14.10.4.5.7/2, 14.10.4.5.7/3
Test Case Name Status Standard Reference PICS Reference History Test Purpose Note Test Setup	 Xmit_max_timer range. MANDATORY 14.2.1.6 14.10.4.5.7/2, 14.10.4.5.7/3 To verify that jabber transmission inhibit starts within the time requir Test setup C.
Test Case Name Status Standard Reference PICS Reference History Test Purpose Note	 Xmit_max_timer range. MANDATORY 14.2.1.6 14.10.4.5.7/2, 14.10.4.5.7/3 To verify that jabber transmission inhibit starts within the time require:

Test Case Name:Jabber reset.Status:MANDATORYStandard Reference:14.10.4.5.7/1, 14.10.4.5.7/4History::Test Purpose:To verify the jabber function reset mechanism.Note::Test Stup:Test stup C.Test Procedure:Apply test signal 3a to the DO circuit of the MAU. Monitor the I cuit, TD circuit, and CI circuits and CS0 is asserted on o circuit), stop the test signal. Wait 249 ms from when the test sig signals are present on the DI and DI circuit. Wait and add 502 ms and verify that CS0 is no longer asserted on the CI circuit and 1 signals are present on the DI circuit and DI circuit. Wait and add 502 ms and verify that CS0 is no longer asserted on the CI circuit and t signals are present on the DI circuit and DI circuit. Wait and add 502 ms and verify that CS0 is no longer asserted on the CI circuit. I the above procedure using test signal 3b.Conformance:If a transmission exceeds xmit, max the jabber function shall in the Loopback function and the transmission of TD_output messa the Transmit function and shall send the CS0 signal on the CI c ± 0.25 s.Test Case ID:1411.06.03Test Case Name:Jabber lockup protection.Standard Reference:14.2.1.6PICS Reference:14.10.4.5.7/5History::Test Stup:To verify the MAU jabber lockup protection.Note::Test setup B.Test Procedure:Apply test signal 26 to the DO circuit of the MAU. Monitor the T circuit Tramins active.<	Test Case ID	: 1411.06.02
Status : MANDATORY Standard Reference : 14.2.1.6 PICS Reference : 14.10.4.5.7/1, 14.10.4.5.7/4 History : : Test Purpose : To verify the jabber function reset mechanism. Note : : Test Setup : Test setup C. Test Procedure : Apply test signal 3a to the DO circuit of the MAU. Monitor the I cuit, TD circuit, and CL circuit and CS0 is asserted on circuit), stop the test signal. Wait 249 ms from when the test signals are present on the D circuit and DL circuit. Wait an add 502 ms and verify that CS0 is no longer asserted on the CL circuit. I the above procedure using test signal 3b. Conformance : If a transmission exceeds xmit_max the jabber function shall in the Loopback function and the transmission of TD_output messas, the Transmist function and shall send the CS0 signal on the CL circuit. In the above procedure using test signal 3b. Conformance : If a transmistion exceeds xmit_max the jabber function shall in the Loopback function and the transmission of TD_output messas, the Transmit function and the transmission of TD_output messas, the Transmit function and shall send the CS0 signal on the CL circuit. It was an ADATORY Status : MANDATORY Status : MANDATORY Status : MANDATORY		
Standard Reference : 14.10.4.5.7/1, 14.10.4.5.7/4 History : : Test Purpose : To verify the jabber function reset mechanism. Note :: : Test Setup : : Test setup for each state of the state of th		
PICS Reference : 14.10.4.5.7/1, 14.10.4.5.7/4 History : To verify the jabber function reset mechanism. Note : Test Setup C. Test Procedure : Apply test signal 3a to the DO circuit of the MAU. Monitor the I cuit, TD circuit, and CI circuit. When jabber is indicated (sign longer present on the DI and TD circuits and CS0 is asserted on circuit), stop the test signal. Wait 249 ms from when the test signals are present on the TD circuit and DI circuit. Water and and 502 ms and verify that CS0 is no longer asserted on the CI circuit. If the above procedure using test signal 3b. Conformance : If a transmission exceeds xmit_max the jabber function shall in the Loopback function and the transmission of TD_output messa, the Transmit function and shall send the CS0 signal on the CI circuit for a time unjab. The value of unjab shall be 0 ± 0.25 s. Test Case ID : 1411.06.03 Test Case Name : Jabber lockup protection. Status : MANDATORY Status : MANDATORY Status : Test setup B. Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T circuit remains active. Conformance : Test setup B. Test Purpose : To verify the MAU jabber lockup protection. Status		
History :: Test Purpose :: To verify the jabber function reset mechanism. Note :: Test Setup :: Test setup C. Test Procedure :: Apply test signal 3a to the DO circuit of the MAU. Monitor the I cuit, TD circuit, and CI circuit. When jabber is indicated (sign longer present on the DI and TD circuits and CS0 is asserted on circuit), stop the test signal. Wait 249 ms from when the test sig- stopped and verify that CS0 is still present on the CI circuit and the signals are present on the TD circuit and DI circuit. Wait an add 502 ms and verify that CS0 is no longer asserted on the CI circuit. If the above procedure using test signal 3b. Conformance :: If a transmission exceeds xmit_max the jabber function shall in the Loopback function and shall send the CS0 signal on the CI c This shall continue until output_idle has been continuously press the DO circuit for a time unjab. The value of unjab shall be 0 ± 0.25 s. Test Case ID :: 1411.06.03 Test Case Name :: Jabber lockup protection. Status :: MANDATORY Standard Reference :: 14.2.1.6 PICS Reference :: 14.2.1.6 PICS Reference :: 14.2.1.6 PICS Reference :: 14.10.4.5.7/5 History :: Test Purpose :: To verify the MAU jabber lockup protection. Note :: Test Setup :: Test setup B. Test Procedure :: Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit remains active. Conformance :: The MAU shall not activate its Jabber function when the repeater s Jabber Lockup Protection function operates at its longest permitte as specified in 9.6.5. 2.1.7 Test group 1411.07 — Iink integrity test functions . Test Group ID :: 1411.07.01 Test Case ID :: 1411.07.01 Test Case ID :: 1411.07.01 Test Case Name :: Link Instegrity Test functions. Test Group Purpose :: To verify the functional characteristics of the link integrity test func- Status :: MANDATORY		
Test Purpose : To verify the jabber function reset mechanism. Note : Test Setup : Test setup C. Test Procedure : Apply test signal 3a to the DO circuit of the MAU. Monitor the I cuit, TD circuit, and CS0 is asserted on circuit), stop the test signal. Wait 249 ms from when the test signals are present on the DI and TD circuit and DI circ		:
Note : Test Setup : Test setup C. Test Procedure : Apply test signal 3a to the DO circuit of the MAU. Monitor the I cuit, TD circuit, and CI circuit. When jabber is indicated (sign longer present on the DI and TD circuits and CS0 is asserted on or circuit), stop the test signal. Wait 249 ms from when the test signal Sm and verify that CS0 is no longer asserted on the CI circuit and the above procedure using test signal 3b. Conformance : If a transmission exceeds xmit_max the jabber function shall in the Loopback function and the transmission of TD_output message the Transmit function and shall send the CS0 signal on the CI or This shall continue until output_idle has been continuously prestive DO circuit for a time unjab. The value of unjab shall be 0 ± 0.25 s. Test Case ID : 1411.06.03 Test Case Name : Jabber lockup protection. Status : MANDATORY Standard Reference : 14.10.4.5.7/5 History : : Test Setup : Test setup B. Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit transmis active. Conformance : Test setup B. Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify		To verify the jabber function reset mechanism.
Test Procedure : Apply test signal 3a to the DO circuit of the MAU. Monitor the 1 cuit, TD circuit, and CI circuit. When jabber is indicated (sign longer present on the DI and TD circuits and CS0 is asserted on circuit), stop the test signal. Wait 249 ms from when the test signals are present on the TD circuit and DI circuit. Wait an add 502 ms and verify that CS0 is no longer asserted on the CI circuit. The above procedure using test signal 3b. Conformance : If a transmission exceeds xmii_max the jabber function shall in the Loopback function and the transmission of TD_output message the Transmit function and shall send the CS0 signal on the CI circuit and the transmit signals are present on the TO circuit and provide the DO circuit for a time unjab. The value of unjab shall be the 0.25 s. Test Case ID : 1411.06.03 Test Case ID : 1411.06.03 Test Case ID : 141.1.06.75 PICS Reference : 14.2.1.6 PICS Reference : 14.2.1.6 PICS Reference : 14.2.1.6 PICS Reference : 14.2.1.6 PICS Reference : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit memains active. Conformance : Test setup B. Test Quite Setup Setup Setup 12.26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabb		
Test Procedure : Apply test signal 3a to the DO circuit of the MAU. Monitor the 1 cuit, TD circuit, and CI circuit. When jabber is indicated (sign longer present on the DI and TD circuits and CS0 is asserted on circuit), stop the test signal. Wait 249 ms from when the test signals are present on the TD circuit and DI circuit. Wait an add 502 ms and verify that CS0 is no longer asserted on the CI circuit. The above procedure using test signal 3b. Conformance : If a transmission exceeds xmii_max the jabber function shall in the Loopback function and the transmission of TD_output message the Transmit function and shall send the CS0 signal on the CI circuit and the transmit signals are present on the TO circuit and provide the DO circuit for a time unjab. The value of unjab shall be the 0.25 s. Test Case ID : 1411.06.03 Test Case ID : 1411.06.03 Test Case ID : 141.1.06.75 PICS Reference : 14.2.1.6 PICS Reference : 14.2.1.6 PICS Reference : 14.2.1.6 PICS Reference : 14.2.1.6 PICS Reference : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit memains active. Conformance : Test setup B. Test Quite Setup Setup Setup 12.26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabb	est Setup	: Test setup C.
Conformance : If a transmission exceeds xmit_max the jabber function shall in the Loopback function and the transmission of TD_output message the Transmit function and shall send the CS0 signal on the CI of This shall continue until output_idle has been continuously press the DO circuit for a time unjab. The value of unjab shall be the 0.25 s. Test Case ID : 1411.06.03 Test Case Name : Jabber lockup protection. Status : MANDATORY Standard Reference : 14.2.1.6 PICS Reference : 14.1.0.4.5.7/5 History : : Test Status : MANDATORY Standard Reference : 14.2.1.6 PICS Reference : 14.1.0.4.5.7/5 History : : Test Purpose : To verify the MAU jabber lockup protection. Note : : Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cur: Verify that the MAU does not enter jabber by verifying that t circuit remains active. Conformance : The MAU shall not activate its Jabber function when the repeater s Jabber Lockup Protection function operates at its longest permitte as specified in 9.6.5. 2.1.7 Test group 1411.07 <	1	: Apply test signal 3a to the DO circuit of the MAU. Monitor the DI circuit, TD circuit, and CI circuit. When jabber is indicated (signals n longer present on the DI and TD circuits and CS0 is asserted on the C circuit), stop the test signal. Wait 249 ms from when the test signal stopped and verify that CS0 is still present on the CI circuit and that n signals are present on the TD circuit and DI circuit. Wait an additiona 502 ms and verify that CS0 is no longer asserted on the CI circuit. Repeated on the CI circuit.
Test Case Name : Jabber lockup protection. Status : MANDATORY Standard Reference : 14.2.1.6 PICS Reference : 14.10.4.5.7/5 History : . Test Purpose : To verify the MAU jabber lockup protection. Note : . Test Purpose : To verify the MAU jabber lockup protection. Note : . Test Setup : Test setup B. Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit remains active. Conformance : The MAU shall not activate its Jabber function when the repeater s Jabber Lockup Protection function operates at its longest permitte as specified in 9.6.5. 2.1.7 Test group 1411.07 — Link integrity test functions. Test Group ID : 1411.07 Test Group Purpose : To verify the functional characteristics of the link integrity test functions. Test Group Purpose : 1411.07.01 Test Case ID : 1411.07.01 Test Case Name :	Conformance	: If a transmission exceeds xmit_max the jabber function shall inhibit the Loopback function and the transmission of TD_output messages b the Transmit function and shall send the CS0 signal on the CI circui This shall continue until output_idle has been continuously present o the DO circuit for a time unjab. The value of unjab shall be 0.5 s
Test Case Name : Jabber lockup protection. Status : MANDATORY Standard Reference : 14.2.1.6 PICS Reference : 14.10.4.5.7/5 History : . Test Purpose : To verify the MAU jabber lockup protection. Note : . Test Setup : Test setup B. Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit remains active. Conformance : The MAU shall not activate its Jabber function when the repeater s Jabber Lockup Protection function operates at its longest permitte as specified in 9.6.5. 2.1.7 Test group 1411.07 — link integrity test functions. Test Group ID : 1411.07 Test Group Name : Link Integrity Test functions. Test Group Purpose : To verify the functional characteristics of the link integrity test functions. Test Case ID : 1411.07.01 Test Case Name : Link loss timer. Status : MANDATORY	est Case ID	: 1411.06.03
Status : MANDATORY Standard Reference : 14.2.1.6 PICS Reference : 14.10.4.5.7/5 History : . Test Purpose : To verify the MAU jabber lockup protection. Note : . Test Purpose : To verify the MAU jabber lockup protection. Note : . Test Setup : Test setup B. Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit remains active. Conformance : The MAU shall not activate its Jabber function when the repeater s Jabber Lockup Protection function operates at its longest permitte as specified in 9.6.5. 2.1.7 Test group 1411.07 — link integrity test functions Test Group ID : 1411.07 Test Group Name : Link Integrity Test functions. Test Group Purpose : To verify the functional characteristics of the link integrity test functions. Test Case ID : 1411.07.01 Test Case ID : 1411.07.01 Test Case Name : <t< td=""><td></td><td></td></t<>		
PICS Reference : 14.10.4.5.7/5 History : . Test Purpose : To verify the MAU jabber lockup protection. Note : . Test Setup : Test setup B. Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit remains active. Conformance : The MAU shall not activate its Jabber function when the repeater s Jabber Lockup Protection function operates at its longest permitte as specified in 9.6.5. Z.1.7 Test group 1411.07 — link integrity test functions Test Group ID : 1411.07 Test Group Name : Link Integrity Test functions. Test Group Purpose : To verify the functional characteristics of the link integrity test functions. Test Case ID : 1411.07.01 Test Case Name : Link loss timer. Status : MANDATORY		
History : Test Purpose : Test Purpose : Test Setup : Test Setup : Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit remains active. Conformance : Test Group 1411.07 — Ink integrity test functions Test Group ID : 1411.07 Test Group Purpose : Test Group ID : 1411.07 Test Group Name : Link Integrity Test functions. Test Group Name : Test Case ID : 1411.07.01 Test Case Name : Link loss timer. Status :	standard Reference	: 14.2.1.6
Test Purpose : To verify the MAU jabber lockup protection. Note : Test Setup : Test setup B. Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit remains active. Conformance : The MAU shall not activate its Jabber function when the repeater s Jabber Lockup Protection function operates at its longest permitte as specified in 9.6.5. Z.1.7 Test group 1411.07 — link integrity test functions Test Group ID : 1411.07 Test Group Name : Link Integrity Test functions. Test Group Purpose : To verify the functional characteristics of the link integrity test functions. Test Case ID : 1411.07.01 Test Case Name : Link loss timer. Status : MANDATORY	ICS Reference	: 14.10.4.5.7/5
Test Purpose : To verify the MAU jabber lockup protection. Note : Test Setup : Test setup B. Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit remains active. Conformance : The MAU shall not activate its Jabber function when the repeater s Jabber Lockup Protection function operates at its longest permitte as specified in 9.6.5. Z.1.7 Test group 1411.07 — link integrity test functions Test Group ID : 1411.07 Test Group Name : Link Integrity Test functions. Test Group Purpose : To verify the functional characteristics of the link integrity test functions. Test Case ID : 1411.07.01 Test Case Name : Link loss timer. Status : MANDATORY	listory	:
Note : Test Setup : Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit remains active. Conformance : The MAU shall not activate its Jabber function when the repeater s Jabber Lockup Protection function operates at its longest permitte as specified in 9.6.5. 2.1.7 Test group 1411.07 — link integrity test functions Test Group ID : 1411.07 Test Group Purpose : To verify the functional characteristics of the link integrity test functions. Test Case ID : 1411.07.01 Test Case Name : Link loss timer. Status : MANDATORY	•	: To verify the MAU jabber lockup protection.
Test Setup : Test setup B. Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit remains active. Conformance : The MAU shall not activate its Jabber function when the repeater s Jabber Lockup Protection function operates at its longest permitte as specified in 9.6.5. 2.1.7 Test group 1411.07 Iink integrity test functions Test Group ID : 1411.07 Test Group Purpose : To verify the functional characteristics of the link integrity test functions. Test Case ID : 1411.07.01 Test Case Name : Link loss timer. Status : MANDATORY	_	
Test Procedure : Apply test signal 26 to the DO circuit of the MAU. Monitor the T cuit. Verify that the MAU does not enter jabber by verifying that t circuit remains active. Conformance : The MAU shall not activate its Jabber function when the repeater s Jabber Lockup Protection function operates at its longest permitte as specified in 9.6.5. 2.1.7 Test group 1411.07 — Link integrity test functions Test Group ID : 1411.07 Test Group Purpose : To verify the functional characteristics of the link integrity test functions. Test Case ID : 1411.07.01 Test Case Name : Link loss timer. Status : MANDATORY		: Test setup B.
Conformance : The MAU shall not activate its Jabber function when the repeater s Jabber Lockup Protection function operates at its longest permitte as specified in 9.6.5. 2.1.7 Test group 1411.07 — link integrity test functions Test Group ID : 1411.07 Test Group Name : Link Integrity Test functions. Test Group Purpose : To verify the functional characteristics of the link integrity test functional characteristics of the link integrity test functional characteristics of the link integrity test functional test Case ID Test Case ID : 1411.07.01 Test Case Name : Link loss timer. Status : MANDATORY		: Apply test signal 26 to the DO circuit of the MAU. Monitor the TD circuit. Verify that the MAU does not enter jabber by verifying that the T
Test Group ID : 1411.07 Test Group Name : Link Integrity Test functions. Test Group Purpose : To verify the functional characteristics of the link integrity test functional characteristeristics of the link integrity test functio	Conformance	: The MAU shall not activate its Jabber function when the repeater s MAU Jabber Lockup Protection function operates at its longest permitted times
Test Group Name : Link Integrity Test functions. Test Group Purpose : To verify the functional characteristics of the link integrity test functional characteristics of test functional characteristics of test functional characteristintest functiona	1.7 Test group 1411.	07 — link integrity test functions
Test Group Purpose : To verify the functional characteristics of the link integrity test functindependent characteristics of the link integrity test	Cest Group ID	: 1411.07
Test Case ID : 1411.07.01 Test Case Name : Link loss timer. Status : MANDATORY	-	
Test Case Name:Link loss timer.Status:MANDATORY	est Group Purpose	: To verify the functional characteristics of the link integrity test function
Test Case Name:Link loss timer.Status:MANDATORY	est Case ID	: 1411.07.01
Status : MANDATORY		
	Standard Reference	: 14.2.1.7

PICS Reference	: 14.10.4.5.8/1
History	:
Test Purpose	: To verify the value of the link_loss timer.
Note	:
Test Setup	: Test setup B.
Test Procedure	: Apply test signal 4 to the DO circuit of the MAU. Monitor the DI circuit and TD circuit. Stop applying the link test pulses to the RD circuit. Mea- sure the time from the last link test pulse to the loss of loopback on the DI circuit.
Conformance	: If neither RD_input nor a link test pulse is received for a time link_loss, the MAU shall enter the Link Test Fail state and cause the input_idle message to be sent on the DI circuit and the TD_idle message to be sent on the TD circuit (Figure 14-6 of ISO/IEC 8802-3 [IEEE Std 802.3]). The value of link_loss shall be between 50 ms and 150 ms.
Test Case ID	: 1411.07.02
Test Case Name	: Acceptance range for consecutive link test pulses.
Status	: MANDATORY
Standard Reference	: 14.2.1.7
PICS Reference	: 14.10.4.5.8/6, 14.10.4.5.8/7
History	:
Test Purpose	: To verify acceptance range for consecutive link test pulses.
Note	:
Test Setup	: Test setup B.
Test Procedure	: Apply power to the MAU. Stop applying the link test pulses to the RD
	circuit. Check that the MAU is in a Link Test Fail state. Monitor the DO circuit and DI circuit. Apply a test signal consisting of 11 link test pulses that are spaced 7.1 ms apart to the RD circuit of the MAU. Apply test signal 1 to the DO circuit of the MAU. Verify loopback presence on the DI circuit. Repeat the test procedure with 24 ms spacing between link test
Conformance	 pulses. Only link test pulses that occur within time link_test_max of each other shall be considered consecutive. The value of link_test_max shall be between 25 ms and 150 ms. In addition, detected pulses that occur within a time link_test_min of a previous pulse or packet shall be ignored while in the Link Test Pass state. In the Link Test Fail state, such pulses shall reset the counted number of consecutive link test pulses to zero. The value of link_test_min shall be between 2 ms and 7 ms.
Test Case ID	: 1411.07.03
Test Case Name	: Link test pulses outside acceptance range (while in Link Test Pass state).
Status	: MANDATORY
Standard Reference	: 14.2.1.7
PICS Reference	: 14.10.4.5.8/8
History	:
Test Purpose	: To verify the rejection range for consecutive link test pulses while the
ĩ	MAU is in the Link Test Pass state.
Note	: This test case is considered untestable. It is not practical to measure and is not considered critical. Even though testing for compliance is not practical, conformance to the standard, by design, is the responsibility of the manufacturer with compliance status to be noted in the PICS.
Test Setup	:
-	

Test Procedure	:
Conformance	: Detected pulses that occur within a time link_test_min of a previous
	pulse or packet shall be ignored while in the Link Test Pass state. The value of link_test_min shall be between 2 ms and 7 ms.
Test Case ID	: 1411.07.04
Test Case Name	: Link test pulses outside acceptance range (not in the Link Test Pass state).
Status	: MANDATORY
Standard Reference	: 14.2.1.7
PICS Reference	: 14.10.4.5.8/9
History	:
Test Purpose	: To verify the rejection range for consecutive link test pulses while the MAU is not in Link Test Pass state.
Note	:
Test Setup	: Test setup B.
Test Procedure	: Apply power to the MAU. Stop applying link test pulses to the RD cir- cuit. Check that the MAU is in a Link Test Fail state. Monitor the DO circuit and DI circuit. Apply a test signal consisting of 11 link test pulses that are spaced 1.9 ms apart to the RD circuit of the MAU. Check that the MAU is still in a Link Test Fail state. Apply test signal 1 to the DO circuit of the MAU. Verify that loopback is disabled. Repeat the test procedure with 151 ms spacing between link test pulses.
Conformance	: Only link test pulses that occur within time link_test_max of each other shall be considered consecutive. The value of link_ test_max shall be between 25 ms and 150 ms. In addition, detected pulses that occur within a time link_test_min of a previous pulse or packet shall be ignored while in the Link Test Pass state. In the Link Test Fail state, such pulses shall reset the counted number of consecutive link test pulses to zero. The value of link_test_min shall be between 2 ms and 7 ms.
Test Case ID	: 1411.07.05
Test Case Name	: Link fail effect on MAU functions.
Status	: MANDATORY
Standard Reference	14.2.1.7
PICS Reference	: 14.10.4.5.8/2-4, 14.10.4.5.8/10-14
History	:
Test Purpose	: To verify that the following MAU functions are disabled, while the MAU is not in the Link Pass state: Transmit, Receive, Loopback, Collision Presence, and SQE test.
Note	: Some of these tests will cause a transition to the Link Test Pass state after the test signal ends. Before continuing the tests, make sure that the MAU under test returns to a Link Test Fail state.
Test Setup	: Test setup N.
Test Procedure	: Apply power to the MAU. For each of the following scenarios, check that the MAU is in a Link Test Fail state before applying the test signal(s) to
	the specified circuit(s):
	(1) Transmit. Apply test signal 1 to the DO circuit of the MAU under test while monitoring the TD circuit for TP_IDL.
	(2) Receive. Apply test signal 1 to the DO circuit of the tester MAU while monitoring the DI circuit of the MAU under test for IDL.
	(3) Loopback. Apply test signal 1 to the DO circuit of the MAU

Conformance	 under test while monitoring the DI circuit of the MAU under test for IDL. (4) Collision Presence. Apply test signal 1 to the DO circuit of the tester MAU and test signal 1 to the DO circuit of the MAU under test to create a collision. Monitor the CI circuit of the MAU under test for IDL. (5) SQE Test. Apply test signal 1 to the DO circuit of the MAU under test. Monitor the CI circuit for no SQE. While the MAU is not in the Link Test Pass state, the Link Integrity Test function shall disable the bit transfer of the Transmit, Receive, and Loopback functions, and the Collision Presence and SQE Test functions.
Test Case ID	: 1411.07.06
Test Case Name	: Link Test Fail Extend state exit.
Status	: MANDATORY
Standard Reference	: 14.2.1.7
PICS Reference	: 14.10.4.5.8/15
History	:
Test Purpose	: To verify that the MAU functions are re-enabled only after the RD and DO circuits become idle.
Note	:
Test Setup	: Test setup N.
Test Procedure	: Apply power to the MAU under test. Check that the MAU under test is
Conformance	 under test. After 1 ms, apply test signal 1 to the DO circuit of the tester MAU. Verify that DI loopback occurs on the second packet from the DC circuit of the MAU under test, but not on the first packet. Re-enabling shall be deferred until the signals on the RD and DO circuits become idle.
2.1.8 Test group 141	1.08 — MAU state machines
Test Group ID	: 1411.08
Test Group Name	: MAU state machines.
1	
Test Group Purpose	: To verify proper operation of the MAU state machines.
1	
Test Group Purpose	 : To verify proper operation of the MAU state machines. : 1411.08.01
Test Group Purpose Test Case ID	: To verify proper operation of the MAU state machines.
Test Group Purpose Test Case ID Test Case Name	 To verify proper operation of the MAU state machines. 1411.08.01 MAU transmit, receive, loopback, and collision state diagram.
Test Group Purpose Test Case ID Test Case Name Status	 To verify proper operation of the MAU state machines. 1411.08.01 MAU transmit, receive, loopback, and collision state diagram. MANDATORY
Test Group Purpose Test Case ID Test Case Name Status Standard Reference	 To verify proper operation of the MAU state machines. 1411.08.01 MAU transmit, receive, loopback, and collision state diagram. MANDATORY Figure 14-3
Test Group Purpose Test Case ID Test Case Name Status Standard Reference PICS Reference	 To verify proper operation of the MAU state machines. 1411.08.01 MAU transmit, receive, loopback, and collision state diagram. MANDATORY Figure 14-3 14.10.4.5.9/1
Test Group Purpose Test Case ID Test Case Name Status Standard Reference PICS Reference History	 To verify proper operation of the MAU state machines. 1411.08.01 MAU transmit, receive, loopback, and collision state diagram. MANDATORY Figure 14-3 14.10.4.5.9/1 To verify the MAU transmit, receive, loopback, and collision presenced
Test Group Purpose Test Case ID Test Case Name Status Standard Reference PICS Reference History Test Purpose	 To verify proper operation of the MAU state machines. 1411.08.01 MAU transmit, receive, loopback, and collision state diagram. MANDATORY Figure 14-3 14.10.4.5.9/1 To verify the MAU transmit, receive, loopback, and collision presence functions. Test case coverage for this test is shown in Figure A1. Use the following test setups for each subtest below:
Test Group Purpose Test Case ID Test Case Name Status Standard Reference PICS Reference History Test Purpose Note	 To verify proper operation of the MAU state machines. 1411.08.01 MAU transmit, receive, loopback, and collision state diagram. MANDATORY Figure 14-3 14.10.4.5.9/1 To verify the MAU transmit, receive, loopback, and collision presence functions. Test case coverage for this test is shown in Figure A1. Use the following test setups for each subtest below: (1) As specified in each individual test case
Test Group Purpose Test Case ID Test Case Name Status Standard Reference PICS Reference History Test Purpose Note	 To verify proper operation of the MAU state machines. 1411.08.01 MAU transmit, receive, loopback, and collision state diagram. MANDATORY Figure 14-3 14.10.4.5.9/1 To verify the MAU transmit, receive, loopback, and collision presence functions. Test case coverage for this test is shown in Figure A1. Use the following test setups for each subtest below: (1) As specified in each individual test case (2) Test setup N
Test Group Purpose Test Case ID Test Case Name Status Standard Reference PICS Reference History Test Purpose Note	 To verify proper operation of the MAU state machines. 1411.08.01 MAU transmit, receive, loopback, and collision state diagram. MANDATORY Figure 14-3 14.10.4.5.9/1 To verify the MAU transmit, receive, loopback, and collision presence functions. Test case coverage for this test is shown in Figure A1. Use the following test setups for each subtest below: (1) As specified in each individual test case (2) Test setup N (3) Test setup P
Test Group Purpose Test Case ID Test Case Name Status Standard Reference PICS Reference History Test Purpose Note	 To verify proper operation of the MAU state machines. 1411.08.01 MAU transmit, receive, loopback, and collision state diagram. MANDATORY Figure 14-3 14.10.4.5.9/1 To verify the MAU transmit, receive, loopback, and collision presence functions. Test case coverage for this test is shown in Figure A1. Use the following test setups for each subtest below: (1) As specified in each individual test case (2) Test setup N (3) Test setup P (4) Test setup O
Test Group Purpose Test Case ID Test Case Name Status Standard Reference PICS Reference History Test Purpose Note	 To verify proper operation of the MAU state machines. 1411.08.01 MAU transmit, receive, loopback, and collision state diagram. MANDATORY Figure 14-3 14.10.4.5.9/1 To verify the MAU transmit, receive, loopback, and collision presence functions. Test case coverage for this test is shown in Figure A1. Use the following test setups for each subtest below: (1) As specified in each individual test case (2) Test setup N (3) Test setup P

: Apply	power to the MAU.	
(1)	Perform the following tests, using the procedure(s) as specified in each test case: 1411.01.04, 1411.02.02, 1411.03.01,	
	1411.04.01, 1411.04.02, 1411.04.04 and 1411.04.05.	
(2)	Check that the MAU under test is in a Link Test Fail state. Mon-	
	itor the DI circuit of the MAU under test. Apply test signal 1 to	
	the DO circuit of the tester MAU. Verify that the test signal	
	does not appear on the DI circuit of the MAU under test.	
(3)	Apply test signal 3a to the DO circuit of the MAU under test.	
	Monitor the DI circuit, RD circuit, and CI circuit of the MAU	
	under test. When jabber is indicated (CS0 is asserted on the CI	
	circuit), apply test signal 1 to the DO circuit of the tester MAU.	
	Verify that the RD test signal appears on the DI circuit of the	
	MAU under test.	
(4)	Monitor the DI circuit, DO circuit, and RD circuit of the MAU	
	under test. Apply test signal 6 to the DO circuit of the tester	
	MAU. Apply test signal 1 to the DO circuit of the MAU under	
	test such that the start and end of frame occurs while test signal	
	6 is active (see Figure 6-2a). Verify that DI is active for the du-	
	ration of test signal 6 on the RD circuit.	
(5)	Monitor the DI circuit, DO circuit, and RD circuit of the MAU	
	under test. Apply test signal 6 to the DO circuit of the MAU un-	
	der test. Apply test signal 1 to the DO circuit of the tester MAU	
	such that the start and end of frame occurs while test signal 6 is	
	active (see Figure 6-2b). Verify that DI is active for the duration of test signal 6 on the DO circuit. Apply IDL to the DO circuit of the MAU. Monitor the CI cir-	
(6)		
	cuit, DI circuit, and TD circuit. Verify that the CI circuit and DI	
	circuit are asserting IDL and the TD circuit is asserting	
	TP_IDL.	
: Meets	the requirements of Figure 14-3.	
: 1411.	08.02	
: Signa	<i>l_quality_error</i> message test function state diagram.	
: CONI	DITIONAL (SQE Test function shall be performed by MAUs	
conne	cted to DTEs and shall not be performed for MAUs connected to	
repeat	ers).	
: Figure	2 14-4	
: 14.10	4.5.9/2	
:		
: To ve	rify the <i>signal_quality_error</i> message test function.	
	ase coverage for this test is shown in Figure A2.	
	ne test setups as specified in each individual test case.	
	m the following tests, using the procedure(s) as specified in each	
	se: 1411.05.01, 1411.05.02, and 1411.05.04.	
: Meets	the requirements of Figure 14-4.	
: 1411	08.03	
	r function state diagram.	
	DATORY	
-	4.5.9/3	
	(1) (2) (3) (3) (4) (4) (5) (6) (6) (6) (6) (7) (6) (7) (6) (7) (6) (7) (7) (7) (7) (7) (7) (7) (7) (7) (7	



a) Test signal applied to tester MAU, then MAU under test



b) Test signal applied to MAU under test, then tester MAU

Figure 6-2 — Test signal application timing for collision state diagram

History	:
Test Purpose	: To verify the jabber function state diagram.
Note	: Test case coverage for this test is shown in Figure A3
Test Setup	: Test setup C.
Test Procedure	: Disable the LTPG, apply power to the MAU, and check that the MAU is
	in a Link Test Fail state.
	 (1) Perform the following tests, using the procedure(s) as specified in each test case: 1411.06.01 and 1411.06.02. (2) Monitor the DI circuit, TD circuit, and CI circuit of the MAU. Apply test signal 3a to the DO circuit of the MAU for at least 151 ms. When jabber is indicated (SQE is asserted on the CI circuit), stop the test signal. Wait for 249 ms, verify that SQE is still asserted on the CI circuit, then reapply the test signal for a duration of 512 bit times. Stop the test signal for a duration of 512 bit
	(3) Monitor the DI circuit, TD circuit, and CI circuit of the MAU. Apply test signal 5 to the DO circuit of the MAU. Verify that the TD signals and DI signals follow DO and that CS0 is not as-
	serted on the CI circuit.
	Enable the LTPG, check that the MAU is in the Link Test Pass state and
	repeat tests (1) and (2) above.
Conformance:	: Meets the requirements of Figure 14-5.
Test Cose ID	. 1411.02.04
Test Case ID	: 1411.08.04
Test Case Name	: Link integrity test function state diagram.
Status	: MANDATORY
Standard Reference	: Figure 14-6
PICS Reference	: 14.10.4.5.9/4
History	:
Test Purpose	: To verify the link integrity test function state diagram.
Note	: Test case coverage for this test is shown in Figure A4.
Test Setup	: Use the following test setups for each subtest below:
	(1) As specified in each individual test case
	(2) Test setup N
	(3) Test setup B
	(4) Test setup M
Test Procedure	: Perform each subtest listed below.
	 Perform the following tests, using the procedure(s) specified in each test case: 1411.01.04, 1411.02.02, 1411.03.01, and 1411.07.01 through 1411.07.06, inclusive. Monitor the DI circuit and TD circuit of the MAU under test. Apply power to the MAU and check that the MAU is in a Link Test Fail state. Apply test signal 1 to the DO circuit of the tester MAU and verify the presence of IDL on the DI circuit of the MAU under test. Apply test signal 1 to the DO circuit of the
	MAU under test within 1 ms and verify that the test signal ap-
	pears on the TD circuit of the MAU under test.

	(3) Monitor the DI circuit. Apply power to the MAU and check that the MAU is in the Link Test Pass state. Apply test signal 2a to the DO circuit of the MAU under test. Stop the transmission of link test pulses onto the RD circuit. After the MAU has entered a Link Test Fail state as indicated by the cessation of DI activi- ty, wait 7.1 ms then send one link test pulse. Apply test signal 1 to the DO circuit of the MAU within 1 ms to 2 ms of the link test pulse. Verify that no loopback signals appear on the DI circuit.
Conformance : M	(4) Monitor the DI circuit of the MAU under test. Apply power to the MAU and check that the MAU is in the Link Test Pass state. Apply test signal 18 to the DO circuit of the tester MAU. Apply test signal 1 to the DO circuit of the MAU under test within 1 ms of the end of the last packet on the RD circuit. Verify that the test signal appears on the DI circuit. Ieets the requirements of Figure 14-6.

6.2.1.9 Test group 1411.09 — isolation requirements

Test Group ID	:	1411.09
Test Group Name	:	Isolation requirements.
Test Group Purpose	:	To verify proper isolation on the MDI leads.

Test Case ID	:	1411.09.01
Test Case Name	:	Isolation, MDI leads to DTE Physical Layer circuits.
Status	:	MANDATORY
Standard Reference	:	14.3.1.1
PICS Reference	:	14.10.4.5.11/1
History	:	
Test Purpose	:	To verify the electrical isolation between the MDI leads and the DTE Physical Layer circuits, including frame ground.
Note	:	Test case 1411.09.02 must be run after this test is completed.
Test Setup	:	Test setup CC.
Test Procedure	:	 Apply one of the following voltages as E_{iso} between each pin of the AUI connector (including PG, the AUI shell) and each pin of the MDI connector. For embedded MAUs, apply E_{iso} between Frame Ground of the MAU (as specified in the PIXIT) and each pin of the MDI connector. (1) 1500 V rms at 50 Hz to 60 Hz for 60 s, applied as specified in 5.3.2 of IEC 60950. (2) 2250 Vdc for 60 s, applied as specified in 5.3.2 of IEC 60950. (3) A sequence of ten 2400 V impulses of alternating polarity, applied at intervals of not less than 1 s. The shape of the impulses shall be 1.2/50 µs, as defined in IEC 60060. Verify that there is no insulation breakdown during the test.
Conformance	:	 The MAU shall provide isolation between the DTE Physical Layer circuits including frame ground and all MDI leads including those not used by 10BASE-T. This electrical separation shall withstand at least one of the following electrical strength tests: (1) 1500 V rms at 50 Hz to 60 Hz for 60 s, applied as specified in 5.3.2 of IEC 60950. (1) 2250 Vdc for 60 s, applied as specified in 5.3.2 of IEC 60950. (2) A sequence of ten 2400 V impulses of alternating polarity, applied at intervals of not less than 1 s. The shape of the impulses

shall be $1.2/50 \ \mu s$ ($1.2 \ \mu s$ virtual front time, $50 \ \mu s$ virtual time of half value), as defined in IEC 60060. There shall be no insulation breakdown, as defined in 5.3.2 of IEC 60950, during the test.

:	1411.09.02
:	Resistance after breakdown test.
:	MANDATORY
:	14.3.1.1
:	14.10.4.5.11/2
:	
:	To verify the resistance between the MDI leads and the DTE Physical Layer circuits, including frame ground.
:	Test case 1411.09.01 must be run prior to this test.
:	Test setup DD.
:	Apply 500 Vdc between each pin of the AUI connector (including PG, the AUI shell) and each pin of the MDI connector. For embedded MAUs, apply 500 Vdc between Frame Ground of the MAU (as specified in the PIXIT) and each pin of the MDI connector. Verify that the dc current is less than 250 μ A.
:	The resistance after the test shall be at least 2 M Ω , measured at 500 Vdc.
	: : :

6.2.1.10 Test group 1411.10 — transmitter specification

Test Group ID	:	1411.10
Test Group Name	:	Transmitter specification.
Test Group Purpose	:	To verify transmitted signal parameters.

Test Case ID Test Case Name Status Standard Reference PICS Reference History Test Purpose	 1411.10.01 TD circuit short-circuit current. MANDATORY 14.3.1.2.7 14.10.4.5.12/12, 14.10.4.5.12/13 To verify the transmitter fault tolerance.
Note	. To verify the transmitter funct toterance.
Test Setup	: Test setup R.
Test Procedure	: Apply power to the MAU. Monitor the peak output current of the TD cir- cuit of the MAU while applying a short circuit across the TD circuit for 10 s. Apply test signal 4 to the DO circuit of the MAU. Continue moni- toring the output current of the TD circuit for an additional 10 s. Remove the short circuit. Verify that, when the fault condition is removed, the cir- cuit operates normally by performing the remainder of the transmitter tests (group ID 1411.10).
Conformance	: Transmitters, when either idle or nonidle, shall withstand without dam- age the application of short circuits across the TD circuit for an indefinite period of time and shall resume normal operation after such faults are re- moved. The magnitude of the current through such a short circuit shall not exceed 300 mA.
Test Case ID	: 1411.10.02
Test Case Name	: Peak differential output voltage on TD circuit.
Status Standard Reference PICS Reference History Test Purpose Note Test Setup Test Procedure Conformance	 MANDATORY 14.3.1.2.1 14.10.4.5.12/1 To verify the TD circuit peak differential output voltage. Test setup B. Apply test signal 1 to the DO circuit of the MAU. Monitor the peak differential voltage on the TD circuit across the 100 Ω load. The peak differential voltage on the TD circuit when terminated with a 100 Ω resistive load shall be between 2.2 V peak and 2.8 V peak for all
--	--
	data sequences.
Test Case ID	: 1411.10.03
Test Case Name	: Harmonic content, all ones signal.
Status	: MANDATORY
Standard Reference	: 14.3.1.2.1
PICS Reference	: 14.10.4.5.12/2
History	
Test Purpose	. To verify the harmonic content at the output of transmitter.
Note	. To verify the narmonic content at the output of transmitter.
Test Setup	: Test setup T.
Test Procedure	Apply test signal 5 to the DO circuit of the MAU. Monitor the harmonic
Test Flocedule	content of the TD circuit signal using the spectrum analyzer.
Conformance	: When the DO circuit is driven by an all ones Manchester signal, each har- monic measured at the output of the transmitter shall be at least 27 dB below the fundamental.
Test Case ID	: 1411.10.04
Test Case Name	: Output waveform, with scaling of voltage template.
Status	: MANDATORY
Standard Reference	: 14.3.1.2.1
PICS Reference	: 14.10.4.5.12/3
History	:
Test Purpose	: To verify the transmitter output equalization.
Note	: See Clause 14, Annex A4.3.1, for measurement details.
Test Setup	: Test setup A.
Test Procedure	: Apply test signal 1 to the DO circuit of the MAU. Monitor the TD circuit
	signal. An oscilloscope set for a zero voltage trigger with a positive slope is allowed to accumulate an eye pattern that must be within the template. Acquisition must be long enough to ensure that all data variations have been observed. When using packetized data, the TP_IDL and the first transmitted bit should be excluded from this measurement. Repeated ap- plications of the test signal may be necessary to acquire enough data to build a definite eye pattern.
Conformance	: The TD transmitter shall provide equalization such that the output waveform shall fall within the template shown in Figure 14-9 for all data sequences. Voltage and time coordinates for inflection points on Figure 14-9 are given in Table 14-1. (Zero crossing points are different for external and internal MAUs. The zero crossings depicted in Figure 14-9 apply to an external MAU.) The template voltage may be scaled by a factor of 0.9 to 1.1, but any scaling below 0.9 or above 1.1 shall not be

allowed. The recommended measurement procedure is described in A4.3.1. Time t = 0 on the template represents a zero crossing, with positive slope, of the output waveform.

Test Case ID Test Case Name	: 1411.10.05: Output waveform with scaling of voltage template (inverted template).
Status	: MANDATORY
Standard Reference	: 14.3.1.2.1
PICS Reference	: 14.10.4.5.12/3
History	
Test Purpose	: To verify the transmitter output equalization.
Note	
Test Setup	: Test setup A.
Test Procedure	: Apply test signal 1 to the DO circuit of the MAU. Monitor the TD circuit signal. An oscilloscope set for a zero voltage trigger with a negative slope is allowed to accumulate an eye pattern that must be within the template. Acquisition must be long enough to ensure that all data variations have been observed. When using packetized data, the TP_IDL and the first transmitted bit should be excluded from this measurement. Repeated applications of the test signal may be necessary to acquire enough data to build a definite eye pattern.
Conformance	: The TD transmitter shall provide equalization such that the output waveform shall fall within the template shown in Figure 14-9 for all data sequences. Voltage and time coordinates for inflection points on Figure 14-9 are given in Table 14-1. (Zero crossing points are different for external and internal MAUs. The zero crossings depicted in Figure 14-9 apply to an external MAU.) The template voltage may be scaled by a factor of 0.9 to 1.1, but any scaling below 0.9 or above 1.1 shall not be allowed. The recommended measurement procedure is described in A4.3.1. Time $t = 0$ on the template represents a zero crossing, with negative slope, of the output waveform.
Test Case ID	: 1411.10.06
Test Case Name	: Start of TP_IDL waveform, with specified loads, with and without the
	cable model.
Status	: MANDATORY
Standard Reference	14.3.1.2.1
PICS Reference	: 14.10.4.5.12/4
History	
Test Purpose	: To verify the characteristics of the transmitter output after transition to idle state.
Note	:
Test Setup	: Test setup D.
Test Procedure	: Apply test signal 1 to the DO circuit of the MAU. Monitor the TD circuit
	signal at the test load for each of the test loads shown in Figure 14-11. Repeat the test without the TPM in the Test Setup and the test loads con- nected directly to the TD circuit.
Conformance	: The TP_IDL shall always start with a positive waveform when a wave- form conforming to Figure 7-12 is applied to the DO circuit. If the last bit transmitted was a CD1, the last transition will be at the bit cell center of the CD1. If the last bit transmitted was a CD0, the PLS will generate an additional transition at the bit-cell boundary following the CD0. After

the zero crossing of the last transition, the differential voltage shall remain within the shaded area of Figure 14-10. Once the differential voltage has gone more negative than -50 mV, it shall not exceed +50 mV. The template requirements of Figure 14-10 shall be met, when measured across each of the test loads defined in Figure 14-11; both with the load connected directly to the TD circuit and with the load connected through the twisted pair model as defined in Figure 14-7 and Figure 14-8.

		· · · · · · · · · · ·
Test Case ID	:	1411.10.07
Test Case Name	:	TD circuit differential output impedance.
Status	:	MANDATORY
Standard Reference	:	14.3.1.2.2
PICS Reference	:	14.10.4.5.12/6
History Text D	:	
Test Purpose	:	To verify the transmitter differential output impedance.
Note	:	See Clause 14, Annex A4.3.2 for measurement details.
Test Setup	:	Test setup Q.
Test Procedure	:	Using the network analyzer, measure the return loss between 5.0 MHz and 10 MHz with 0.5 MHz steps, utilizing a reference resistance of 100 Ω . Calculate the return loss using a reference resistance of 85 Ω and 111 Ω .
Conformance	:	The differential output impedance as measured on the TD circuit shall be such that any reflection, due to differential signals incident upon the TD circuit from a simplex link segment having any impedance within the range specified in 14.4.2.2, shall be at least 15 dB below the incident, over the frequency range of 5.0 MHz to 10 MHz. This return loss shall be maintained at all times when the MAU is in the power-on state, in- cluding when the TD circuit is sending TP_IDL.
Test Case ID	:	1411.10.08
Test Case Name	:	Common-mode to differential-mode conversion.
Status	:	MANDATORY
Standard Reference	:	14.3.1.2.4
PICS Reference	:	14.10.4.5.12/9
History	:	
Test Purpose	:	To verify the transmitter impedance balance over the frequency range of $1.0-21$ MHz.
Note	:	The balance of the test equipment (such as the matching of the 147 Ω resistors) must exceed that required of the transmitter.
Test Setup	:	Test setup E.
Test Procedure	:	Apply power. Apply a 1 MHz sine wave with a 15 V peak amplitude to represent the $E_{\rm cm}$ signal and monitor the differential voltage at the TD circuit, $E_{\rm dif}$, ignoring the Link Test Pulses. In steps of 2 MHz, increase the frequency up to a maximum of 21 MHz. For each step, calculate the common-mode to differential-mode impedance balance as 20 log ₁₀ ($E_{\rm cm}$ / $E_{\rm dif}$).
Conformance	:	The common-mode to differential-mode impedance balance of the transmitter shall exceed $29 - 17 \log_{10} (f/10) dB$ (where <i>f</i> is the frequency in MHz) over the frequency range 1.0 MHz to 20 MHz.
Test Case ID	:	1411.10.09

Test Case Name Status Standard Reference PICS Reference History Test Purpose Note Test Setup Test Procedure Conformance	 TD circuit common-mode output voltage. MANDATORY 14.3.1.2.5 14.10.4.5.12/10 To verify the common-mode output voltage of the transmitter. The balance of the test equipment (such as the matching of the 47.5 Ω resistors) must exceed that required of the transmitter. Test setup F. Apply test signal 1 to the DO circuit of the MAU. Measure the common-mode output voltage <i>E</i>_{cm}. The magnitude of the total common-mode output voltage of the transmitter, <i>E</i>_{cm}, measured as shown in Figure 14-14, shall be less than 50 mV peak.
Test Case ID Test Case Name Status Standard Reference PICS Reference	 1411.10.10 Transmitter common-mode rejection, 15 V peak 10.1 MHz sinusoid. MANDATORY 14.3.1.2.6 14.10.4.5.12/11
History Test Purpose Note	: To verify the transmitter common-mode rejection.
Test Setup Test Procedure	 Test setup E. Apply test signal 1 to the DO circuit of the MAU. Monitor the differential voltage at the TD circuit, <i>E</i>_{dif}. Establish a baseline jitter value by measuring the edge jitter at the TD circuit with a 0 V <i>E</i>_{cm} input. Apply a 15 V peak amplitude 10.1 MHz sine wave to represent the <i>E</i>_{cm} signal and measure the edge jitter.
Conformance	: The application of $E_{\rm cm}$ as shown in Figure 14-13 shall not change the dif- ferential voltage at the TD circuit, $E_{\rm dif}$, by more than 100 mV for all data sequences. Additionally, the edge jitter added by the application of $E_{\rm cm}$ shall be no more than 1.0 ns. $E_{\rm cm}$ shall be a 15 V peak 10.1 MHz sine wave.
Test Case ID Test Case Name	 : 1411.10.11 : Link test pulse waveform, with specified loads, with and without the cable model.
Status	: MANDATORY
Standard Reference PICS Reference	: 14.3.1.2.1 : 14.10.4.5.12/5
History	: 14.10.4.3.12/3
Test Purpose Note	: To verify the characteristics of the Link Test Pulse waveform.
Test Setup	: Test setup G.
Test Procedure	: Monitor the TD circuit signal at the test load for each of the test loads shown in Figure 14-11. Repeat the test without the TPM in the test setup and with the test loads connected directly to the TD circuit.
Conformance	: The link test pulse shall be a single positive (TD+ lead positive with re- spect to TD- lead) pulse, which falls within the shaded area of Figure 14- 12. Once the differential output voltage has become more negative than

-50 mV, it shall remain less than +50 mV. The template requirements of Figure 14-12 shall be met, when measured across each of the test loads defined in Figure 14-11; both with the load connected directly to the TD circuit and with the load connected through the twisted-pair model as defined in Figure 14-7 and Figure 14-8.

Test Case ID	: 1411.10.12
Test Case Name	: Transmitter output timing jitter with cable model.
Status	: MANDATORY
Standard Reference	: 14.3.1.2.3
PICS Reference	: 14.10.4.5.12/7
History	:
Test Purpose	: To verify the jitter added by the MAU.
Note	:
Test Setup	: Test setup A.
Test Procedure	: Apply test signal 6 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Using the oscilloscope, measure the jitter of the zero crossings on the TD circuit. Disregard the first bit transmitted on the TD circuit and Start Of Idle (SOI). Set the oscilloscope to trigger on the DO circuit signal zero crossing with positive slope. Observe the zero cross- ings 8 BT and 8.5 BT from the triggering zero crossing. An external MAU is compliant when all zero crossings fall within the time intervals $8.0 \text{ BT} \pm 7 \text{ ns}$ and $8.5 \text{ BT} \pm 7 \text{ ns}$.
Conformance	: The jitter added to the signal on the DO circuit as it propagates through
	the MAU and twisted pair model shall be no more than ± 3.5 ns.
	-
Test Case ID	: 1411.10.13
Test Case Name	: Transmitter output timing jitter without cable model.
Status	: MANDATORY
Standard Reference	: 14.3.1.2.3
PICS Reference	: 14.10.4.5.12/8
History	
Test Purpose	: To verify the jitter added by the MAU when directly driving a 100 Ω re-
	sistive load.
Note	
Test Setup	: Test setup B.
Test Procedure	 Apply test signal 6 to the DO circuit of the MAU. Monitor the DO circuit and TD circuit. Using the oscilloscope, measure the jitter of the zero crossings on the TD circuit. Disregard the first bit transmitted on the TD circuit and Start Of Idle (SOI). Set the oscilloscope to trigger on the DO circuit signal zero crossing with positive slope. Observe the zero crossings 8 BT and 8.5 BT from the triggering zero crossing. An external MAU is compliant when all zero crossings fall within the time intervals 8.0 BT ± 16 ns and 8.5 BT ± 16 ns.
Conformance	: The MAU shall add no more than ± 8 ns of jitter to the signal received on the DO circuit, when the TD circuit is directly driving a 100 Ω resis- tive load.
Test Case ID	: 1411.10.14
Test Case Name	: Transmitter fault tolerance, impulse.
Status	: MANDATORY

Standard Reference	: 14.3.1.2.7
PICS Reference	: 14.10.4.5.12/14
History	
Test Purpose	To verify the transmitter fault tolerance when a high-voltage impulse
1	applied to the transmitter when idle and nonidle.
Note	: The impulse shape should be adjusted while applied to the test object
	per IEC 60060.
Test Setup	: Test setup AA.
Test Procedure	: Apply an IEC standard full impulse voltage of positive polarity, with
Conformance	 peak value of 1000 V, a virtual front time of 300 ns, and virtual time half value of 50 µs as E_{cm} to the test setup. Repeat the test using a neg tive polarity impulse. Apply test signal 5 to the DO circuit of the MA Repeat the previous test procedure (both polarities). Verify that the tran mitter still operates normally by performing the transmitter test gro tests (group ID 1411.10). Transmitters, when either idle or nonidle, shall withstand without data.
	age a 1000 V common-mode impulse applied at $E_{\rm cm}$ of either polarity (indicated in Figure 14-15). The shape of the impulse shall be 0.3/50 (300 ns virtual front time, 50 µs virtual time of half value), as defined IEC 60060.
Test Case ID	: 1411.10.15
Test Case Name	: Power cycle effect on TD circuit.
Status	: MANDATORY
Standard Reference	: 14.3.2.3
PICS Reference	: 14.10.4.5.12/15
History	:
Test Purpose	: To verify proper operation of the TD circuit with power cycling.
Note	: Extraneous signal on the TD circuit is defined to be greater than ± 50 m
Test Setup	: Test setup A.
Test Procedure	: Monitor the TD circuit of the MAU. Turn the power to MAU off, th on several times. Verify that no extraneous signals appear on the TD c cuit.
Conformance	: The MAU shall not introduce extraneous signals on the TD circuits du
	ing normal power-up and power-down.
2.1.11 Test group 14 ⁷	ing normal power-up and power-down.
Test Group ID	in the second se
Test Group ID Test Group Name	 i11.11 — receiver specification i 1411.11 i Receiver specification.
Test Group ID	in the second se
Test Group ID Test Group Name	 i11.11 — receiver specification i 1411.11 i Receiver specification.
Test Group ID Test Group Name Test Group Purpose	 if a factor of the specification if a factor of the specification. if a consure correct input signal handling of the receiver.
Test Group ID Test Group Name Test Group Purpose ————————————————————————————————————	 i11.11 — receiver specification i 1411.11 i Receiver specification. i To ensure correct input signal handling of the receiver. i 1411.11.01
Test Group ID Test Group Name Test Group Purpose Test Case ID Test Case Name	 if if i
Test Group ID Test Group Name Test Group Purpose Test Case ID Test Case Name Status Standard Reference	 if if i
Test Group ID Test Group Name Test Group Purpose Test Case ID Test Case Name Status Standard Reference PICS Reference	 if if i
Test Group ID Test Group Name Test Group Purpose Test Case ID Test Case Name Status Standard Reference PICS Reference History	#11.11 — receiver specification : 1411.11 : Receiver specification. : To ensure correct input signal handling of the receiver. : 1411.11.01 : RD circuit fault tolerance, short circuit. : MANDATORY : 14.3.1.3.6 : 14.10.4.5.13/11
Test Group ID Test Group Name Test Group Purpose Test Case ID Test Case Name Status Standard Reference PICS Reference	 if if i
Test Group ID Test Group Name Test Group Purpose Test Case ID Test Case Name Status Standard Reference PICS Reference History	#11.11 — receiver specification : 1411.11 : Receiver specification. : To ensure correct input signal handling of the receiver. : 1411.11.01 : RD circuit fault tolerance, short circuit. : MANDATORY : 14.3.1.3.6 : 14.10.4.5.13/11

802.3-2001	IEEE CONFORMANCE TEST METHODOLOGY FOR IEEE STANDARDS FOR LAN MA
Test Procedure	: Apply power to the MAU. Apply a short circuit across the RD circuit 10 s. Verify that when the fault condition is removed the circuit oper
Conformance	 normally by performing all other receive tests (Group ID 1411.11). Receivers shall tolerate the application of short circuits between the le of the RD circuit for an indefinite period of time without damage shall resume normal operation after such faults are removed.
Test Case ID	: 1411.11.02
Test Case Name	: RD circuit idle detection.
Status	: MANDATORY
Standard Reference	: 14.3.1.3.3
PICS Reference	: 14.10.4.5.13/8
History	
Test Purpose	. To verify that the receiver detects the idle condition.
Note	· · · · · · · · · · · · · · · · · · ·
Test Setup	: Test setup K.
Test Procedure	: Apply test signal 14 to the RD circuit of the MAU. Monitor the DI circ
rest i locedule	and verify proper start of idle on the DI circuit.
Conformance	: The idle condition shall be detected within 2.3 BT of the last low-to-l
	transition at the receiver.
Test Case ID	: 1411.11.03
Test Case Name	: RD circuit signal acceptance.
Status	: MANDATORY
Standard Reference	: 14.3.1.3.1
PICS Reference	: 14.10.4.5.8/17, 14.10.4.5.13/1, 14.10.4.5.13/2
History	:
Test Purpose	To verify the receiver differential input voltage acceptance.
Note	:
Test Setup	: Test setup K.
Test Procedure	: Apply test signals 7a–b, 8a–b, 9, and 10 to the RD circuit of the M. Monitor the DI circuit and RD circuit. Verify that the pulses appear the DI circuit.
Conformance	: Differential signals received on the RD circuit that are within the er
	lope of Figure 14-16 and 14-17, and have a maximum zero crossing jup to ± 13.5 ns from the ideal, shall be sent to the DI circuit.
Test Case ID	: 1411.11.04
Test Case Name	: RD circuit differential noise rejection.
Status	: MANDATORY
Standard Reference	: 14.3.1.3.2
PICS Reference	: 14.10.4.5.13/5-7
History	:
Test Purpose	: To verify the receiver noise immunity.
Note	:
Test Setup	: Test setup K.
Test Procedure	: Apply test signals 11a-g, 12a-c, and 13a-d to the RD circuit of
	MAU. Monitor the DI circuit and RD circuit. For each test signal, ve
	that the DI circuit remains idle.
Conformance	: The receiver, while in the Idle state, shall reject as <i>RD_input</i> the folloing signals:

filter, would produce a peak magnitude less than 300 mV. The filter is a 3-pole low-pass Butterworth with a 3 dB cut off at 15 MHz.

- (2) All continuous sinusoidal signals of amplitude less than 6.2 V peak-to-peak and frequency less than 2 MHz.
- (3) All sine waves of single-cycle duration, starting with phase 0 or 180 degrees, and of amplitude less than 6.2 V peak-to-peak, where the frequency is between 2 MHz and 15 MHz. For a period of 4 BT before and after this single cycle, the signal shall be less than 300 mV when measured through the filter specified in (1) above.

Test Case ID	: 1411.11.05
Test Case Name	: RD circuit differential input impedance.
Status	: MANDATORY
Standard Reference	: 14.3.1.3.4
PICS Reference	: 14.10.4.5.13/9
History	:
Test Purpose	: To verify the differential input impedance.
Note	:
Test Setup	: Test setup I.
Test Procedure	: Set the network analyzer to produce 2.5 V peak into 100 Ω . Measure the differential input impedance between 5.0 MHz and 10 MHz with 0.5 MHz steps, utilizing a reference resistance of 100 Ω . Calculate the return loss using a reference resistance of 85 Ω and 111 Ω .
Conformance	: The differential input impedance shall be such that any reflection, due to differential signals incident upon the RD circuit from a twisted pair having any impedance within the range specified in 14.4.2.2 shall be at least 15 dB below the incident, over the frequency range of 5.0 MHz to 10 MHz.
Test Case ID	: 1411.11.06
Test Case Name	: RD circuit common-mode rejection.
Status	: MANDATORY
Standard Reference	: 14.3.1.3.5
PICS Reference	: 14.10.4.5.13/10
History	:
Test Purpose	: To verify the receiver common-mode rejection.
Note	:
Test Setup	: Test setup J.
Test Procedure	: Apply power to the MAU. Apply test signal 15, as differential input signal E_s , to the test fixture such that a 585 mV signal, E_{dif} is present on the RD circuit of the MAU. Monitor the differential input signal, E_{dif} , at the RD circuit of the MAU and the DI circuit. Apply test signal 17 as E_{cm} . Check the DI circuit for the proper state and for jitter.
Conformance	: Receivers shall assume the proper state on DI for any differential input signal E_s that results in a signal E_{dif} that meets 14.3.1.3.1 even in the presence of common-mode voltages E_{cm} (applied as shown in Figure 14-18). E_{cm} shall be a 25 V peak-to-peak square wave, 500 kHz or lower in frequency, with edges no slower than 4 ns (20–80%). Additionally E_{cm} shall contribute no more than 2.5 ns of edge jitter to the signal transmitted on the DI circuit. The combination of the receiver timing jitter of 14.3.1.3.1 and the common-mode induced jitter are such that the MAU

shall add no more then 4.0 ns of edge jitter to $E_{\rm s}$ before sending the signal on the DI circuit.

Test Case ID Test Case Name	: 1411.11.09 : Receiver fault tolerance, impulse.
Test Case ID	. 1411 11 00
Conformance	 MAU. Monitor the DI circuit and RD circuit. Using the oscilloscope measure the jitter of the zero crossings. Disregard the first bit sent on the DI circuit. Set the oscilloscope to trigger on the RD circuit signal zero crossing with positive slope. Observe the zero crossings 8 BT and 8.5 BT from the triggering zero crossing. An external MAU is compliant when all zero crossings fall within the time intervals 8.0 BT ± 3 ns and 8.5 BT ± 3 ns. The MAU receiver shall add no more than ±1.5 ns jitter to the received signal before sending the signal to the DI circuit.
Test Procedure	: Apply power to the MAU. Apply test signal 16 to the RD circuit of the MAU. Monitor the DL circuit and RD circuit. Using the assillation
Test Setup	: Test setup H.
Note	:
Test Purpose	: To verify that jitter added by MAU receiver does not exceed ± 1.5 ns.
History	
PICS Reference	: 14.10.4.5.13/3
Standard Reference	: 14.3.1.3.1
Status	: MANDATORY
Test Case Name	: Received signal added jitter.
Test Case ID	: 1411.11.08
Conformance	: The receiver, when presented with a signal meeting the requirements o 14.2.1.1 and within the envelope of Figure 14-12, shall accept it as a link test pulse.
~ .	width.
	(2) As in Figure 14-12 with maximum allowed amplitude and pulse
	width of 0.60 BT and maximum undershoot.
	The link test pulses used shall have the following characteristics: (1) As in Figure 14-12 with a peak amplitude of 585 mV, a pulse
	nals on the TD circuit.
	that the MAU has entered the Link Test Pass state by monitoring the sig
	immediately apply test signal 1 to the DO circuit of the MAU and check
	shape and amplitude as described below. After at least 10 link test pulses
	Link Test Fail state. Start sending link test pulses on the RD circuit. The link test pulses shall occur within 25 ms to 150 ms of each other and have
	any input on the RD circuit for at least 10 s. Check that the MAU is in a Link Test Fail state. Start sending link test pulses on the RD circuit. The
Test Procedure	: Apply power to the MAU. Monitor the DI circuit and TD circuit. Stop
Test Setup	: Test setup B.
Note	:
Test Purpose	: To verify the receiver acceptance of link test pulses.
History	:
PICS Reference	: 14.10.4.5.13/4
Standard Reference	: 14.3.1.3.2
Status	: MANDATORY
Test Case Name	BD circuit link test pulse acceptance
Test Case Name	: RD circuit link test pulse acceptance.

Status	:	MANDATORY
Standard Reference	:	14.3.1.3.6
PICS Reference	:	14.10.4.5.13/12
History	:	
Test Purpose	:	To verify the receiver fault tolerance when a high-voltage impulse is applied to the receiver.
Note	:	The impulse shape should be adjusted while applied to the test object as per IEC 60060.
Test Setup	:	Test setup BB.
Test Procedure	:	Apply an IEC standard full-impulse voltage of positive polarity with a peak value of 1000 V, a virtual front time of 300 ns, and virtual time to half value of 50 μ s as $E_{\rm cm}$ to the test setup. Repeat the test using a negative polarity impulse. Verify that the receiver still operates normally by performing the receiver test group tests (group ID 1411.11).
Conformance	:	Receivers shall withstand without damage a 1000 V common-mode impulse of either polarity ($E_{impulse}$ as indicated in Figure 14-19). The shape of the impulse shall be 0.3/50 µs (300 ns virtual front time, 50 µs virtual time of half value), as defined in IEC 60060.

6.2.1.12 Test group 1411.12 — AUI signal characteristics

Test Group ID Test Group Name Test Group Purpose	: : :	1411.12 AUI signal characteristics. To ensure correct signaling characteristics of the AUI.
Test Case ID	:	1411.12.01
Test Case Name Status	:	Labeled signaling rate. CONDITIONAL (Only tested if the AUI is implemented and available for testing).
Standard Reference	:	7.3.2
PICS Reference	:	14.10.4.6.1/1
History	:	
Test Purpose	:	To verify that the MAU is correctly labeled with the actual signaling rate used with that device.
Note	:	
Test Setup	:	None.
Test Procedure	:	Visually check the MAU label for an indication that the signalling rate is 10 Mb/s.
Conformance	:	To facilitate the configuration of operational systems, DTE and MAU devices shall be labeled with the actual signaling rate used with that device.
Test Case ID	:	1411.12.02
Test Case Name	:	CS0 signal frequency (on CI).
Status	:	CONDITIONAL (Only tested if the AUI is implemented and available for testing).
Standard Reference	:	7.3.1.2
PICS Reference	:	14.10.4.6.1/2
History	:	
Test Purpose	:	To verify the frequency of the CS0 signal.
Note	:	
Test Setup	:	Test setup C.

IEEE Std 1802.3-2001	IEEE CON	FORMANCE TEST METHODOLOGY FOR IEEE STANDARDS FOR LAN MAN
Test Procedure	:	Apply test signal 3b to the DO circuit of the MAU. Monitor the CI circuit. Measure the frequency of the CS0 signal.
Conformance	:	The tolerance on CI is BR \pm 15%.
Test Case ID	:	1411.12.03
Test Case Name	:	CS0 signal duty cycle.
Status	:	CONDITIONAL (Only tested if the AUI is implemented and available for testing).
Standard Reference	:	7.3.1.2
PICS Reference	:	14.10.4.6.1/3
History	:	
Test Purpose	:	To verify the duty cycle of the CS0 signal.
Note	:	
Test Setup	:	Test setup C.
Test Procedure	:	Apply test signal 3b to the DO circuit of the MAU. Monitor the CI cir-
		cuit. Measure the duty cycle of the CS0 signal.
Conformance	:	The nominal duty cycle is 50/50 and shall be no worse than
Comornance	·	60/40.
6.2.1.13 Test group 1	411.13 —	DI and CI driver characteristics
Test Group ID		1411.13
Test Group Name	•	DI and CI driver characteristics.
Test Group Purpose	· ·	To ensure correct operation of the AUI DI and CI drivers.
Test Gloup I utpose	•	To ensure correct operation of the AOT DI and CI drivers.
Test Case ID		1411.13.01
Test Case ID Test Case Name	•	AUI driver differential output voltage.
Status	:	CONDITIONAL (Only tested if the AUI is implemented and available
Status	·	for testing).
Standard Reference	:	7.4.1.1
PICS Reference		14.10.4.6.2/1-4
History		
Test Purpose		To verify the correct differential output voltage.
Note	•	$T_{\rm j} = 4 \text{ ns} [2 \times (1.5 \text{ ns MAU}-DTE jitter + 0.5 \text{ ns source jitter})].$
Test Setup	•	Test setup U.
Test Procedure	•	Using a test load of 73 $\Omega \pm 1\%$ in parallel with 50 μ H $\pm 1\%$, monitor the
rest i locedule	•	CI circuit and DI circuit of the MAU under test. Monitor the current into
		the test loads. Apply test signal 1 to the DO circuit of the MAU under
		test. Apply test signal 1 to the DO circuit of the tester MAU to create a
		collision.
		(1) During collision, verify that the signals on the CI circuit and DI
		circuit meet the requirements of Figure 7-11 by using the fol-
		lowing procedure. Construct a template representing the shaded
		area of Figure 7-11 using the zero crossings as reference points.
		Once constructed, the template may be shifted along the time
		axis in order to accommodate differences in the 10–50% and
		50–90% transition times. Verify that time T_2 is BT ± 4 ns or BT/
		2 ± 4 ns. Find the peak value of V_{dm} . This is V_{max} . Find the min-
		imum value of $V_{\rm dm}$ during the period between the shaded re-
		gions for the waveform s rising and falling transitions (time T1
		in Figure 7-11). This minimum value is V_{\min} . Verify that V_{\max}
		is less than 1315 mV, that V_{\min} is greater than 450 mV, and that

 $V_{\text{max}}/V_{\text{min}}$ is less than 1.37. Measure the V_{dm} 24 ns after the zero crossing and verify that it remains less than 1170 mV and within the template.

- (2) Observe the DI circuit signals for 2 bit times after the last lowto-high transition of the packet. Verify that the differential output voltage is at least 380 mV during that time.
- (3) Observe the DI circuit signals 80 bit times after the last low-tohigh transition of the packet. Verify that the output voltage is $\leq \pm 40 \text{ mV}$ differential and the current into the load is $\leq 4 \text{ mA}$.
- (4) Observe the CI circuit signals for 2 bit times after the last lowto-high transition of CS0. Verify that the differential output voltage is at least 380 mV during that time.
- (5) Observe the CI circuit signals 80 bit times after the last low-tohigh transition of CS0. Verify that the output voltage is $\leq \pm 40$ mV differential and the current into the load is ≤ 4 mA.

Repeat the test using a test load of 83 Ω \pm 1% in parallel with 50 μH \pm 1%.

- The following conformance statements are applicable as noted.
 - (1) For (1) above: The value of $V_{\rm dm}$ into either of the two test loads identified above (R = 73 Ω or 83 $\Omega \pm 1\%$) at the interface connector of the driving unit shall satisfy conditions defined by values $V_{\rm min}$ and $V_{\rm max}$ shown in Figure 7-11 for signals in between BR and BR/2 meeting the frequency and duty cycle tolerances specified for the signal being driven. $V_{\rm max}$ shall be < 1315 mV, $V_{\rm min}$ shall be > 450 mV, $V_{\rm max}/V_{\rm min}$ shall be < 1.37. $V_{\rm dm}$ shall remain < 1170 mV 24 ns after a zero crossing. The waveform shall remain within the shaded area limits.
 - (2) For (2) through (5): When a driver, connected to the appropriate two test loads identified above, enters the idle state, it shall maintain a minimum differential output voltage of at least 380 mV for at least 2 bit times after the last low-to-high transition. The driver differential output voltage shall then approach within 40 mV of 0 V within 80 bit times. In addition, the current into the appropriate test load shall be limited in magnitude to 4 mA within 80 bit times. Undershoot, if any, upon reaching 0 V shall be limited to -100 mV. See Figure 7-12.

Test Case ID Test Case Name	:	1411.13.02 AUI driver requirements after idle.
Status		CONDITIONAL (Only tested if the AUI is implemented and available
Status	·	for testing).
Standard Reference	:	7.4.1.2
PICS Reference	:	14.10.4.6.2/5
History	:	
Test Purpose	:	To verify the signal characteristics of the first bit transmitted after idle.
Note	:	
Test Setup	:	Test setup U.
Test Procedure	:	Using a test load of 73 $\Omega \pm 1\%$ in parallel with 50 μ H $\pm 1\%$, monitor the
		CI circuit and DI circuit of the MAU under test. Apply test signal 1 to the
		DO circuit of the MAU under test. Apply test signal 1 to the DO circuit
		of the tester MAU to create a collision. Verify that the second bit trans-
		mitted on the DI circuit and CI circuit meets the requirements of 7.4.1.1
		and Figure 7-11. Repeat the test using a test load of 83 $\Omega \pm 1\%$ in parallel

Conformance

·

Conformance	When the driver becomes nonidle after a period of idle on the interface circuit, the differential output voltage at the interface connector shall meet the requirements of 7.4.1.1 beginning with the second bit transmitted. The first bit send over the driver circuit may contain phase violations or invalid data.
Test Case ID	: 1411.13.03
Test Case Name	: AUI driver common-mode output voltage, ac.
Status	: CONDITIONAL (Only tested if the AUI is implemented and available for testing).
Standard Reference	: 7.4.1.3
PICS Reference	: 14.10.4.6.2/6
History	:
Test Purpose	: To verify the ac common-mode output voltage of the AUI drivers.
Note	: The balance of the test equipment (such as the matching of the 39 Ω resistors) must exceed that required of the transmitter.
Test Setup	: Test setup EE.
Test Procedure	 Apply test signals 4 and 25 to the DO circuit of the MAU under test. In each case, apply test signal 1 to the DO circuit of the tester MAU to create a collision. Measure the ac common-mode output voltage E_{cm} on the DI circuit and CI circuit of the MAU under test using Filter 1, then Filter 2. The filter is connected across the circuit under test (DI or CI) and circuit VC.
Conformance	: The magnitude of the ac component of the common-mode output voltage of the driver, measured between the midpoint of a test load consisting of a pair of matched $39 \ \Omega \pm 1\%$ resistors and circuit VC, as shown in Figure 7-13, shall not exceed 2.5 V peak from 30 Hz to 40 kHz and 160 mV peak from 40 kHz to BR.
Test Case ID	: 1411.13.04
Test Case Name	: AUI driver differential output voltage, open circuit.
Status	: CONDITIONAL (Only tested if the AUI is implemented and available for testing).
Standard Reference	: 7.4.1.4
PICS Reference	: 14.10.4.6.2/7
History	:
Test Purpose	: To verify the open circuit differential output voltage.
Note	:
Test Setup	: Test setup W.
Test Procedure	: Apply test signal 1 to the DO circuit of the MAU under test. Apply test signal 1 to the DO circuit of the tester MAU to create a collision. Measure the open circuit differential output voltage, E_{dif} , on the DI circuit and CI circuit of the MAU under test.
Conformance	: The differential output voltage into an open circuit, measured at the in- terface connector of the driving unit, shall not exceed 13 V peak.
Test Case ID	: 1411.13.05
Test Case Name	: AUI driver common-mode output voltage, dc.
Status	: CONDITIONAL (Only tested if the AUI is implemented and available for testing).
Standard Reference	: 7.4.1.5

		1410			
PICS Reference	:	14.10.4	4.6.2/8		
History Test Purpose		To ver	ify the dc common-mod	le output voltage of	the ALII drivers
Note	:		lance of the test equipm		
	•) must exceed that requi		
Test Setup	:	Test se	-		
Test Procedure	:		test signal 1 to the DO		
		-	1 to the DO circuit of the		
			e de common-mode ou		the DI circuit and CI
Conformance			of the MAU under test.		n mada autnut valtaga
Comornance	:		agnitude of the dc compo driver, measured betwee		
			of matched 39 $\Omega \pm 1\%$ re		
			hall not exceed 5.5 V.		
Test Case ID		1411.1	3.06		
Test Case Name	:		river fault tolerance whi	le idle.	
Status	:	COND	ITIONAL (Only tested	if the AUI is imple	mented and available
		for test	0/		
Standard Reference	:	7.4.1.6			
PICS Reference	:	14.10.4	4.6.2/9, 14.10.4.6.2/10		
History Test Providence	:	Т	C. 41 A T IT duinnen Consta	4 . 1	
Test Purpose Note	:	10 ver	ify the AUI driver fault	tolerance when Idle	
Test Setup	:	Test se	tun X		
Test Procedure	:		or the current output of t	the switch A lead an	d switch B lead.
		(1)	Connect the switch A		
			outputs of the MAU u	under test. Apply th	e various fault condi-
			tions (see below), in tu	rn, for 10 s each and	observe that when all
			fault conditions are re		
			performing tests 1411.		
			ify that the output cur		
		(2)	output under any fault Connect the switch A		-
		(2)	outputs of the MAU u		
			tions (see below), in tu		
			fault conditions are re		
			performing tests 1411.		
			ify that the output cur		
			output under any fault		-
					settings
			Fault condition	Lead A	Lead B
			1	1	1
			2	4	3
			3	3	4
			4	4	4
			5	2	3
			6	3	2

Conformance	:	Any single driver in the inte signal, shall tolerate the appl switch settings in Figure 7-1 is removed, the operation of 7.4.1.1 through 7.4.1.5, shall In addition, the magnitude of driver under any of the fa 150 mA.	ication of each of the far 4 indefinitely; and, after the driver, according to the not be impaired. 5 the output current from	ults specified by the r the fault condition the specifications of either output of the
Test Case ID Test Case Name Status Standard Reference PICS Reference History Test Purpose Note Test Setup Test Procedure		 outputs of the MAU circuit of the MAU tions (see below), in all fault conditions by performing tests Verify that the outp tial output under a 150 mA. (2) Connect the switch outputs of the MAU circuit of the MAU tions (see table below when all fault condimally by performing clusive. Verify that 	ed if the AUI is implem	switch B lead. the DI-A and DI-B signal 4 to the DO various fault condi- d observe that when it operates normally 11.13.05, inclusive. hinal of the differen- ss than or equal to the CI-A and CI-B signal 3a to the DO various fault condi- ch and observe that circuit operates nor- ugh 1411.13.05, in- ither terminal of the
		to 150 mA.	Switch se	ettinas
		Fault condition	Lead A	Lead B
		1	1	1
		2	4	3
		3	3	4
		4	4	4
		5	2	3
		6	3	2
		7	2	2
		8	2 3	3
Conformance	:	Any single driver in the inte signal, shall tolerate the appl switch settings in Figure 7-1 is removed the operation of	rface, when idle or driv ication of each of the far 4 indefinitely; and, after	ing any permissible ults specified by the r the fault condition

is removed, the operation of the driver, according to the specifications of

7.4.1.1 through 7.4.1.5, shall not be impaired. In addition, the magnitude of the output current from either output of the driver under any of the fault conditions specified shall not exceed 150 mA.

Test Group ID	:	1411.14
Test Group Name	:	DO receiver characteristics.
Test Group Purpose	:	To ensure correct operation of the AUI DO circuit.
Test Case ID	:	1411.14.01
Test Case Name	:	DO receiver threshold when unsquelched.
Status	:	CONDITIONAL (Only tested if the AUI is implemented and available for testing).
Standard Reference	:	7.4.2.1
PICS Reference	:	14.10.4.6.3/1
History	:	
Test Purpose	:	To verify the DO receiver sensitivity.
Note	:	This parameter is not directly testable because the receiver state is not directly observable and is immaterial if the DO circuit remains in the squelched state. Even though testing for compliance is not practical conformance to the standard, by design , is the responsibility of the man ufacturer with compliance status to be noted in the PICS.
Test Setup	:	
Test Procedure	:	
Conformance	:	When the receiving interface circuit at the interface connector of the receiving equipment is driven by a differential input signal at either BR of BR/2 meeting the frequency and duty cycle tolerances specified for the receiving circuit, when the A lead is 160 mV positive with respect to the B lead, the interface is in the HI state, and when the A lead is 160 mV negative with respect to the B lead, the interface circuit is in the LO state. The receiver output shall assume the intended HI and LO states for the corresponding input conditions.
Test Case ID	:	1411.14.02
Test Case Name	:	DO receiver threshold while in the Idle state.
Status	:	CONDITIONAL (Only tested if the AUI is implemented and available
		for testing).
Standard Reference	:	14.3.2.1
PICS Reference	:	14.10.4.6.3/2
History	:	
Test Purpose	:	To verify the DO receiver squelching.
Note	:	Test and a D
Test Setup	:	Test setup B.
Test Procedure	:	Apply test signal 20 to the DO circuit of the MAU. Monitor the TD ci cuit. Monitor the TD circuit for correct state.
Conformance	:	Additionally, the AUI DO receiver, while in the Idle state, shall reject a input waveform of less than ± 160 mV differential.

002.3-2001	IEEE CONFORMANCE LEST METHODOLOGT FOR IEEE STANDARDS FOR LAN MAN
Test Case Name	: High-to-idle transition on DO circuit.
Status	: CONDITIONAL (Only tested if the AUI is implemented and available
	for testing).
Standard Reference	: 7.4.2.5, 14.3.1.2.1
PICS Reference	: 14.10.4.6.3/3
History	:
Test Purpose	: To verify that the DO receiver correctly recognizes idle.
Note	:
Test Setup	: Test setup D, using Load 1 of Figure 14-11.
Test Procedure	: Apply test signal 23a to the DO circuit of the MAU. Monitor the TD circuit. Verify that the idle signal matches the template of Figure 14-10. Re-
Conformanaa	peat the test using test signal 23b.
Conformance	: The receiving unit shall take precautions to ensure that a high-to-idle transition is not falsely interpreted as an idle-to-nonidle transition, even in the presence of signal droop due to ac coupling in the interface driver or receiver circuits.
Test Case ID	: 1411.14.04
Test Case Name	: DO circuit differential input impedance.
Status	: CONDITIONAL (Only tested if the AUI is implemented and available
	for testing).
Standard Reference	: 7.4.2.2
PICS Reference	: 14.10.4.6.3/4
History:	
Test Purpose	: To verify the input impedance of the DO receiver.
Note Total Cat	: The duration M
Test Setup	: Test setup Y.
Test Procedure	: Using the network analyzer, measure the input impedance (magnitude and phase) of the DO circuit of the MAU at a frequency of 10 MHz and an amplitude of 500 mV.
Conformance	: The ac differential input impedance for AUI receivers located in MAUs shall have a real part of 77.83 $\Omega \pm 6\%$, with the sign of the imaginary part positive, and the phase angle of the impedance in degrees ≤ 0.0338 times the real part of the impedance when measured with a 10 MHz sine wave.
Test Case ID	: 1411.14.05
Test Case Name	: DO circuit common-mode range, ac.
Status	: CONDITIONAL (Only tested if the AUI is implemented and available
0. 1 15 0	for testing).
Standard Reference	: 7.4.2.3
PICS Reference	: 14.10.4.6.3/5
History Test Purpose	To varify the AULDO receiver as common mode renge
Test Purpose Note	 To verify the AUI DO receiver ac common-mode range. Proper output state implies correct polarity with respect to input data. Set
INOLE	the required voltage at the function generator before connecting it to the test setup.
Test Setup	: Test setup Z.
Test Procedure	: Apply test signal 6, as differential input signal E_s , to the test fixture. Monitor the differential input signal E_{dif} at the DO circuit of the MAU and the TD circuit. In succession, apply test signals 21a through 21g as
Conformana	
Comormance	. when the receiving interface circuit at the receiving equipment is driven
	 Test setup Z. Apply test signal 6, as differential input signal E_s, to the test fixt Monitor the differential input signal E_{dif} at the DO circuit of the M

IEEE CONFORMANCE TEST METHODOLOGY FOR IEEE STANDARDS FOR LAN MAN

IEEE Std 1802.3-2001

		by a differential input signal at either BR or BR/2 meeting the frequency and duty cycle tolerances specified for the circuit being driven, the re- ceiver output shall assume the proper output state as specified in 7.4.2.1, in the presence of a peak common-mode ac sine wave voltage either of from 30 Hz to 40 kHz referenced to circuit VC in magnitude from 0 V to 3 V, or in magnitude 0 mV to 200 mV for ac voltages of from 40 kHz to BR as shown in Figure 7-15.
Test Case ID	:	1411.14.06
Test Case Name	:	DO circuit total common-mode range.
Status	:	CONDITIONAL (Only tested if the AUI is implemented and available for testing).
Standard Reference	:	7.4.2.4
PICS Reference	:	14.10.4.6.3/6, 14.10.4.6.3/7
History	:	
Test Purpose	:	To verify the AUI DO receiver total common-mode range and common- mode current limit.
Note	:	Proper output state implies correct polarity with respect to input data. Set the required voltage at the function generator before connecting it to the test setup.
Test Setup	:	Test setup Z.
Test Procedure	:	Apply test signal 6, as differential input signal E_s , to the test fixture. Monitor the differential input signal E_{dif} at the DO circuit of the MAU and the TD circuit. In succession, apply test signals 22a through 22n as E_{cm} . Check the TD circuit for proper state.
Conformance	:	When the receiving interface circuit at the receiving equipment is driven by a differential input signal at either BR or BR/2 meeting the frequency and duty cycle tolerances specified for the circuit being driven, the re- ceiver output shall assume the proper output state as specified in 7.4.2.1, in the presence of a total common-mode voltage, dc plus ac, referenced to circuit VC in magnitude from 0 V to 5.5 V, as shown in the test setup of Figure 7-15. The ac component shall not exceed the requirements of 7.4.2.3. The receiver shall be so designed that the magnitude of the current from the common-mode voltage source used in the test shall not exceed 1 mA.
Test Case ID		1411.14.07
Test Case Name	:	IDL detection, DO circuit.
Status	:	CONDITIONAL (Only tested if the AUI is implemented and available for testing).
Standard Reference	:	7.3.1.1, 14.3.1.2.1
PICS Reference	:	14.10.4.6.3/8
History	:	
Test Purpose	:	To verify AUI DO receiver IDL detection.
Note	:	A MAU that passes test case 1411.14.03 is considered conformant.
Test Setup	:	Test setup D, using Load 1 of Figure 14-11.
Test Procedure	:	Apply test signal 23a to the DO circuit of the MAU. Monitor the TD circuit. Verify that the idle signal matches the template of Figure 14-10. Repeat the test using test signal 23b.
Conformance	:	The IDL condition shall be detected within 1.6 bit times at the receiving device.

Test Case ID Test Case Name Status	::	1411.14.08 Requirements after idle, DO c CONDITIONAL (Only tested for testing).		emented and available
Standard Reference PICS Reference History Test Purpose Note	: : : :	 7.4.2.5, 14.2.1.1 14.10.4.6.3/9 To verify that the AUI DO rec From an external perspective i of the AUI receive circuit (DO if test cases 1411.01.02 and 14 sumed to be in conformance. 	t is difficult to separ D) and those of the l	ate the internal effects MAU TD circuit, thus
Test Setup Test Procedure Conformance	: :	Test setup B. Perform tests 1411.01.02 and The conformance statements of in addition to the following: W period of idle on the interface the output of the receiver shall for the device incorporating the meeting the jitter specification	of 1411.01.02 and 1 When the receiver be circuit, the characte I stabilize within the ne receiver so that it	ecomes nonidle after a eristics of the signal at startup delay allowed is not prevented from
Test Case ID Test Case Name Status Standard Reference PICS Reference History Test Purpose Note Test Setup Test Procedure		 1411.14.09 DO circuit fault tolerance. CONDITIONAL (Only tested for testing). 7.4.2.6 14.10.4.6.3/10, 14.10.4.6.3/11 To verify receiver fault tolerant Test setup X. Monitor the current output of connect the TPG from the DO switch A and switch B leads to under test. Apply the various for 10 s each and observe that circuit operates normally by 1411.14.08, inclusive. Verify the differential input under an 3 mA. 	the switch A lead and circuit of the MAU u o the DO-A and DO- fault conditions (see when all fault condi y performing tests that the input current my fault condition is	nd switch B lead. Dis- inder test. Connect the -B inputs of the MAU table below), in turn, tions are removed, the 1411.14.01 through t on either terminal of a less than or equal to
				settings
		Fault condition	Lead A	Lead B
		1 2	1 4	1 3
		2	4	5

Conformance	:	Any single receiver in the interface shall tolerate the application of each
		of the faults specified by the switch settings in Figure 7-16 indefinitely,
		and, after the fault condition is removed, the operation of the receiver
		according to the specifications of 7.4.2.1 through 7.4.2.6 shall not be
		impaired.
		In addition, the magnitude of the current into either input of the receiver
		under any of the fault conditions specified shall not exceed 3 mA.

Test Group ID : 1411.15 Test Group Name : Power consumption. To ensure that the power consumption is not excessive. Test Group Purpose Test Case ID : 1411.15.01 Test Case Name Power surge limitation and duration. : Status CONDITIONAL (Only tested if the AUI is implemented and available · for testing). Standard Reference : 14.3.2.3 PICS Reference 14.10.4.6.4/1, 14.10.4.6.4/2 : History Test Purpose To verify the power-on surge current characteristics. Note Test setup A. Test Setup : Test Procedure Monitor the current in the VP circuit of the MAU. Measure the peak • surge current, $I_{\rm p}$, and the duration, $T_{\rm w}$, during which the current exceeds the larger of 0.5 A or $0.5 \times I_p$. Conformance : Following power-on, the surge current drawn by the MAU shall be such that $I_p \times T_w$ is less than or equal to 2×10^{-3} A·s, where I_p is the peak surge current and $T_{\rm w}$ is the time during which the current exceeds the larger of 0.5 A or $0.5 \times I_{\rm p}$. Test Case ID 1411.15.02 : Test Case Name Steady-state current. : CONDITIONAL (Only tested if the AUI is implemented and available Status • for testing). Standard Reference 14.3.2.3 : PICS Reference 14.10.4.6.4/3 • History Test Purpose : To verify the steady-state current characteristics. Note Test Setup Test setup A. Test Procedure Monitor the current in the VP circuit of the MAU. Measure the current drawn by the MAU 100 ms following the application of power. Continue monitoring the VP current while applying test signal 5 to the DO circuit of the MAU. Conformance After 100 ms following power-on, the current drawn by the MAU shall : not exceed 0.5 A when powered by the AUI.

6.2.1.15 Test group 1411.15 — power consumption

IEEE Std 1802.3-2001	IEEE CONFORMANCE TEST METHODOLOGY FOR IEEE STANDARDS FOR LAN MAN
Test Case ID Test Case Name Status Standard Reference	 1411.15.03 Voltage source range and current limited supplies. CONDITIONAL (Only tested if the AUI is implemented and available for testing). 14.3.2.3, 7.5.2.5
PICS Reference History	: 14.10.4.6.4/4, 14.10.4.6.4/5
Test Purpose Note	To verify proper operation with current limited sources.
Test Setup Test Procedure	 As specified in the individual test cases. Set the current limit control on the power supply to limit at 500 mA. Perform test cases 1411.01.01 through 1411.01.06, 1411.02.01 through 1411.02.05, 1411.13.01 through 1411.13.05, and 1411.14.01 through 1411.14.06.
Conformance	 The following conformance statements apply: (1) The MAU shall be capable of operating from all possible voltage sources, including those current limited to 0.5 A, as supplied by the DTE or repeater through the resistance of all permissible AUI cables. (2) The Voltage Plus (VP) circuit is an optional circuit that may be sourced from the DTE. If this circuit is sourced from the DTE, it shall be capable of operating at one fixed level between +12 Vdc -6% and +15 Vdc +5% with respect to circuit VC for all current from 0 mA to 500 mA.
Test Case ID Test Case Name Status	 1411.15.04 Power cycle and low VP circuit behavior. CONDITIONAL (Only tested if the AUI is implemented and available
Standard Reference PICS Reference History	for testing). : 14.3.2.3, 7.5.2.5 : 14.10.4.6.4/6, 14.10.4.6.4/7
Test Purpose Note	 To verify proper operation with low voltage sources and power cycling. Extraneous signal on the TD circuit is defined to be greater than ±50 mV; extraneous signal on the CI and DI circuits is defined to be greater than ±40 mV.
Test Setup	: Test setup A.
Test Procedure	 Monitor the TD circuit, CI circuit, and DI circuit of the MAU. (1) Turn the power to MAU off and on several times. Verify that no extraneous signals appear on the TD, CI, or DI circuits. (2) Apply power to the MAU, then adjust the voltage on circuit VP from +15.75 V down to 0.25 V in 0.5 V steps at a rate of change of 1 step per second. Adjust the voltage from 0.25 V to +15.75 V in 0.5 V steps at a rate of change of 1 step pensure that no extraneous signals are introduced on the TD circuit.
Conformance	 The following conformance statements apply: (1) The MAU shall not introduce extraneous signals on the TD, CI, or DI circuits during normal power-up and power-down. (2) MAU designers are cautioned that protection means employed by power sources may cause the voltage at signal VP to drop below the minimum operational voltage specified without going completely to zero volts when loads drawing in excess of the

current supplied are applied between VP and VC. Adequate provisions shall be made to ensure that such a condition does not cause the MAU to disrupt the medium.

6.2.1.16 Test group 1411.16 — circuit termination

Test Group ID Test Group Name Test Group Purpose	 1411.16 Circuit termination. To ensure that the circuit terminations have the proper impedance and coupling to circuit VC.
Test Case ID	: 1411.16.01
Test Case Name	: Impedance and coupling to circuit VC.
Status	: CONDITIONAL (Only tested if the AUI is implemented and available for testing).
Standard Reference	: 7.5.2.8
PICS Reference	: 14.10.4.6.5/2, 14.10.4.6.5/3
History	:
Test Purpose	: To verify that the circuit shield pins are capacitively coupled to VC with an impedance magnitude of $< 5 \Omega$.
Note	:
Test Setup	: Test setup Y, with the network analyzer connected as in the test procedure.
Test Procedure	: Using the network analyzer, measure the impedance between pins 1, 4, 11, and 14 and pin VC at a frequency of 5 MHz. Verify that the magnitude of the impedance is less than 5 Ω and the phase angle is $-90^{\circ} \pm 20^{\circ}$.
Conformance	 Individual pin terminations shall meet the following requirements: Pins 1, 4, 11, 14 connected to logic ground in the DTE. Pins 1, 4, 11, 14 capacitively coupled to VC in MAU. Impedance to ground < 5 Ω at lowest operational BR/2 in the MAU and at highest BR in the DTE.
Test Case ID	: 1411.16.02
Test Case Name	: Common-mode termination.
Status	: CONDITIONAL (Only tested if the AUI is implemented and available for testing).
Standard Reference	: 7.5.2.6
PICS Reference	: 14.10.4.6.5/1
History	:
Test Purpose	: To verify that all common-mode terminations are made with respect to circuit VC.
Note	: This test case is considered untestable. Due to the different possible methods of termination, it is not practical to measure or test. Even though testing for compliance is not practical, conformance to the standard, by design , is the responsibility of the manufacturer with compliance status to be noted in the PICS.
Test Setup	:
Test Procedure	:
Conformance	: Also, all common-mode terminators for AUI circuits shall be made to circuit VC.

Test Group ID	:	1411.17
Test Group Name	:	Safety requirements.
Test Group Purpose	:	To verify general safety.
Test Case ID	:	1411.17.01
Test Case Name	:	Safety Grounding Path.
Status	:	CONDITIONAL (Only tested if the AUI is implemented and availab for testing).
Standard Reference	:	14.7.2.2
PICS Reference	:	14.10.4.5.15/1
History	:	
Test Purpose	:	To verify presence of a safety grounding path.
Note	:	The details of this test procedure are beyond the scope of this standard See the PIXIT or applicable standard(s) for further information.
Test Setup	:	
Test Procedure	:	
Conformance	:	Any safety grounding path for the MAU shall be provided through the circuit PG of the AUI connection.
Test Case ID	:	1411.17.02
Test Case Name	:	General Safety.
Status	:	MANDATORY.
Standard Reference	:	14.7.1
PICS Reference	:	14.10.4.5.15/3
History	:	
Test Purpose	:	To verify conformance to IEC 60950.
Note	:	<i>The details of this test procedure are beyond the scope of this standar</i> <i>See the PIXIT or applicable standard(s) for further information.</i>
Test Setup	:	
Test Procedure	:	
Conformance	:	All equipment meeting this standard shall conform to IEC 60950.
Test Case ID	:	1411.17.03
Test Case Name	:	Application of telephony voltages.
Status	:	MANDATORY.
Standard Reference	:	14.7.2.4
PICS Reference	:	14.10.4.5.15/4
History	:	To see the second secon
Test Purpose Note	:	To verify no safety hazard exists when telephony voltages are applied. The details of this test procedure are beyond the scope of this standar See the PIXIT or applicable standard(s) for further information.
Test Setup		see the 1 1A11 of applicable standard(s) for further information.
Test Procedure	•	
Conformance	:	Although 10BASE-T equipment is not required to survive such wirin hazards without damage, application of any of the above voltages sha not result in any safety hazard.

6.2.2 Basic interconnection test group

1411.18 Test Group ID : Test Group Name Mechanical characteristics, MDI. : Test Group Purpose To ensure that the proper MDI connector is installed. • Test Case ID 1411.18.01 : Test Case Name MDI connector. : Status : MANDATORY. Standard Reference 14.5.1 • PICS Reference 14.10.4.5.14/1 : History • Test Purpose : To verify the MDI connector configuration and dimensions. Note Test Setup : None. Test Procedure Visually check the connector type and gender. Verify that the connector : is an eight-pin jack as per IEC 60603-7. Conformance Eight-pin connectors meeting the requirements of Section 3 and Figure 1 : through Figure 5 of IEC 60603-7 shall be used as the mechanical interface to the twisted-pair segment. The plug connector shall be used on the twisted-pair link segment and the jack on the MAU. Test Case ID 1411.18.02 : Test Case Name MDI connector contact assignment. • Status MANDATORY. : Standard Reference 14.5.1 : PICS Reference : 14.10.4.5.14/2-6 History Test Purpose To verify the MDI connector contact assignment. : Note Test Setup : None. Test Procedure Check that the MDI connector has the pin assignment shown in the table · below. Conformance The following table shows the assignment of signals to connector : contacts. Contact MDI signal 1 TD+ 2 TD-3 RD+ 6 RD-Test Case ID 1411.18.03 ٠ Test Case Name Crossover function indication. : Status : CONDITIONAL (Only tested if the crossover function is implemented). Standard Reference 14.5.2 : PICS Reference 14.10.4.5.14/7 : History Test Purpose : To verify proper connector marking when the crossover function is

6.2.2.1 Test group 1411.18 — mechanical characteristics, MDI

implemented.

IEEE Std 1802.3-2001	IEEE COI	NFORMANCE TEST N	IETHODOLOGY FOF	RIEEE STANDARDS FOR LAN MAN
Note Test Setup Test Procedure Conformance	::	Additionally, the	MDI connector for	presence of a "X". a MAU that implements the cross- graphical symbol "X".
Test Case ID Test Case Name Status Standard Reference PICS Reference History Test Purpose Note		CONDITIONAL 14.5.2 14.10.4.5.14/8-11 To verify the MI function is impler	DI connector conta	t. crossover function is implemented). ct assignment when the crossover
Test Setup Test Procedure	:	None. Check that the MI below.	DI connector has the	e pin assignment shown in the table
Conformance	:	The following ta contacts.	ble shows the ass	signment of signals to connector
		1	TD+	-
		2	TD-	4
		3	RD+	-
		6	RD-	4
		3	RD+	

6.2.2.2 Test group 1411.19 — mechanical characteristics, AUI

Test Group ID	:	1411.19
Test Group Name	:	Mechanical characteristics, AUI.
Test Group Purpose	:	To ensure that the proper AUI connector is installed.
Test Case ID	:	1411.19.01
Test Case Name	:	AUI connector physical dimensions.
Status	:	CONDITIONAL (Only tested if the AUI is implemented and available
		for testing).
Standard Reference	:	7.6.1, 7.6.2
PICS Reference	:	14.10.4.6.6/1
History	:	
Test Purpose	:	To verify the AUI connector configuration and dimensions.
Note	:	
Test Setup	:	None.
Test Procedure	:	Visually check the connector gender. Measure the dimensions against IEC 60807-2.
Conformance	:	A 15-pole male connector having the mechanical mateability dimensions as specified in IEC 60807-2 shall be used for the line interface connector.
Test Case ID		1411.19.02
Test Case Name	:	AUI connector locking posts and mounting.
Status	:	CONDITIONAL (Only tested if the AUI is implemented and available
	•	

	for testing).
Standard Reference	: 7.6.1
PICS Reference	: 14.10.4.6.6/5
History	
Test Purpose	To verify the existence and dimensions of the AUI connector locking
rest r urpose	mechanism.
Note	
Note Total Catal	Norma
Test Setup	: None.
Test Procedure	: Visually check the connector for the presence of locking posts. Measure the locking post dimensions against Figure 7-18. Verify the connector mounting against Figure 7-20.
Conformance	: All female connectors shall have the slide latch, and all male connectors shall have the locking posts (as defined in Figures 7-18, 7-19, and 7-20) as the retention system.
Test Case ID	: 1411.19.03
Test Case Name	: AUI connector pin occupancy.
Status	: CONDITIONAL (Only tested if the AUI is implemented and available
	for testing).
Standard Reference	: 7.6.3
PICS Reference	: 14.10.4.6.6/6-21
History	. 17.10.7.0.0/0 21
Test Purpose	. To verify the existence of the AUI connector pins for the AUI circuits.
Note	. To verify the existence of the Aor connector phils for the Aor encurs.
Test Setup	: None.
Test Procedure	: Visually check the AUI connector on the MAU for the presence of con-
	nector pins at positions 1, 2, 3, 4, 5, 6, 9, 10, 11, 12, 13, and 14.
Conformance	: All pins are present for circuits and shields as defined by the PICS.
Test Case ID	: 1411.19.04
Test Case Name	: AUI connector shield life.
Status	: CONDITIONAL (Only tested if the AUI is implemented and available
	for testing).
Standard Reference	: 7.6.2
PICS Reference	: 14.10.4.6.6/2, 14.10.4.6.6/4
History	:
Test Purpose	: To verify the AUI connector shield life.
Note	: Since this test may be destructive, it is recommended that it be performed
	last.
Test Setup	: None.
Test Procedure	: Using a female AUI connector, mate and unmate to the AUI connector
Test Trocedure	on the MAU for a minimum of 500 cycles. Measure the resistance be- tween the male front shell and the female connector shell.
Conformance	: The resistance of the cable shield to equipment chassis shall not exceed 5 m Ω , after a minimum of 500 cycles of mating and unmating.

6.3 Test setups, signals, and adapters description

This subclause describes the test setups, test signals, adapters, and instruments used in the abstract test suite.

6.3.1 Test signal definitions

Unless otherwise stated, all AUI–DO signals shall have a 56-bit preamble as defined in 4.2.5 of ISO/IEC 8802-3 and Start Frame Delimiter (SFD) preceding the test pattern and a start of idle (SOI) following the test pattern with nominal AUI amplitude (1V peak) and edge transition times (0.2 V/ns) into a 78 Ω resistive load. In addition, unless otherwise stated, all MAU–RD signals are defined across a 100 Ω resistive load when driven from a 100 Ω source impedance, have a peak amplitude of 585 mV, and a tolerance on pulse widths of ±1 ns. A cross-reference table listing test signals and test cases is shown in A1.2.

Signal number	Signal description
1	An AUI–DO signal consisting of a single frame of 512 bits of pseudo- random data.
2a	An AUI–DO signal consisting of repeating frames of 512 bits of pseudo- random data separated by a 4.7 μ s inter-packet gap with a peak amplitude of 375 mV.
2b	An AUI–DO signal consisting of repeating frames of 512 bits of pseudo- random data separated by a 4.7 μ s inter-packet gap with a peak amplitude of 565 mV.
2c	An AUI–DO signal consisting of repeating frames of 512 bits of pseudo- random data separated by a 4.7 μ s inter-packet gap with a peak amplitude of 750 mV.
2d	An AUI–DO signal consisting of repeating frames of 512 bits of pseudo- random data separated by a 4.7 μ s inter-packet gap with a peak amplitude of 940 mV.
2e	An AUI–DO signal consisting of repeating frames of 512 bits of pseudo- random data separated by a 4.7 μ s inter-packet gap with a peak amplitude of 1130 mV.
2f	An AUI–DO signal consisting of repeating frames of 512 bits of pseudo- random data separated by a 4.7 μ s inter-packet gap with a peak amplitude of 1315 mV.
3a	A continuous 5 MHz square wave with a peak amplitude of 375 mV.
3b	A continuous 10 MHz square wave with a peak amplitude of 375 mV.
4	An AUI–DO signal consisting of repeating frames of 1518 bytes of alter- nating 1s and 0s with a 9.6 µs inter-packet gap.
5	An AUI–DO signal consisting of repeating sequences of preamble and SFD followed by Manchester-encoded 1s lasting for 19 ms, followed by a 9.6 µs gap.
6	An AUI–DO signal consisting of a single frame of 1518 bytes of pseudo- random data with a minimum pattern length of 511 bits. Amplitude of 318 mV and maximum edge transition times.
7a	A MAU–RD signal consisting of five pairs of sequences of six alternating polarity pulses with a peak amplitude of 585 mV, when measured at the MDI, with a rising edge described by 585 mV * $\sin(2\pi * t/PW)$, and a falling edge described by 585 mV * $\sin(2\pi(t - PW/2)/PW)$, where PW is either 73 ns or 127 ns. The first sequence has a pulse width of 73 ns on the positive polarity and 127 ns on the negative polarity. The second sequence has a pulse width of 127 ns on the positive polarity and 73 ns on the negative polarity. These five pairs of sequences are followed by a continuous series of a repeating pair of sequences of six alternating polarity one-half cycle sine-wave pulses with a peak amplitude of 585 mV when measured at the MDI. The first sequence has a pulse width of 23 ns (+1,-0 ns) on the positive polarity and 77 ns on the negative polarity. The second sequence

has a pulse width of 77 ns on the positive polarity and 23 ns (+1, -0 ns) on the negative polarity. (See Figure 6-3. Also see Figure 14-16 of ISO/IEC 8802-3). [NOTE — This signal is equivalent to 60 cycles of a maximally jittered 5 MHz signal (30 cycles of maximum jitter in each direction) followed by a maximally jittered 10 MHz signal, all at minimum amplitude.] A MAU–RD signal consisting of five pairs of sequences of six alternating polarity pulses with a peak amplitude of 585 mV, when measured at the MDI, with a rising edge described by 585 mV * $sin(2\pi * t/PW)$, and a falling edge described by 585 mV * $sin(2\pi(t - PW/2)/PW)$, where PW is either 73 ns or 127 ns. The first sequence has a pulse width of 127 ns on the positive polarity and 73 ns on the negative polarity. The second sequence has a pulse width of 73 ns on the positive polarity and 127 ns on the negative polarity. These five pairs of sequences are followed by a continuous series of a repeating pair of sequences of six alternating polarity one-half cycle sine-wave pulses with a peak amplitude of 585 mV when measured at the MDI. The first sequence has a pulse width of 77 ns on the positive polarity and 23 ns (+1, -0 ns) on the negative polarity. The second sequence has a pulse width of 23 ns (+1, -0 ns) on the positive polarity and 77 ns on the negative polarity. (See Figure 6-3. Also see Figure 14-16 of ISO/IEC 8802-3). [NOTE — This signal is equivalent to 60 cycles of a maximally jittered 5 MHz signal (30 cycles of maximum jitter in each direction) followed by a maximally jittered 10 MHz signal, all at minimum amplitude.] A MAU-RD signal consisting of a repeating pair of sequences of five alternating polarity trapezoidal pulses with a peak amplitude of 3.1 V, when measured at the MDI, and a rise and fall slope of 0.5 V/ns. The first sequence has a pulse width of 23 ns (+1, -0 ns) on the positive polarity and 77 ns on the negative polarity. The second sequence has a pulse width of 77 ns on the positive polarity and 23 ns (+1, -0 ns) on the negative polarity. (See Figure 6-4. Also see Figure 14-16 of ISO/IEC 8802-3). A MAU-RD signal consisting of a continuous series of repeating pair of sequences of five alternating polarity trapezoidal pulses with a peak amplitude of 3.1 V, when measured at the MDI, and a rise and fall slope of 0.5 V/ns. The first sequence has a pulse width of 77 ns on the positive polarity and 23 ns (+1, -0 ns) on the negative polarity. The second sequence has a pulse width of 23 ns (+1, -0 ns) on the positive polarity and 77 ns on the negative polarity. (See Figure 6-4. Also see Figure 14-16 of ISO/IEC 8802-3). A MAU-RD signal consisting of a continuous 10 MHz sine wave with a peak amplitude of 585 mV when measured at the MDI. A MAU-RD signal consisting of a continuous series of a repeating pair of sequences of five alternating polarity trapezoidal pulses with a peak amplitude of 3.1 V, when measured at the MDI, and a rise and fall slope of 0.5 V/ns. The first sequence has a pulse width of 127 ns on the positive polarity and 73 ns on the negative polarity. The second sequence has a pulse width of 73 ns on the positive polarity and 127 ns on the negative polarity. (See Figure 6-5. Also see Figure 14-17 of ISO/IEC 8802-3). A MAU-RD signal consisting of a continuous 1 MHz sine wave with a peak amplitude of 299 mV when measured across a 121 Ω resistive load. A MAU-RD signal consisting of a continuous 5 MHz sine wave with a peak amplitude of 299 mV when measured across a 121 Ω resistive load. A MAU-RD signal consisting of a continuous 10 MHz sine wave with a peak amplitude of 312 mV when measured across a 121 Ω resistive load. A MAU-RD signal consisting of a continuous 15 MHz sine wave with a peak amplitude of 423 mV when measured across a 121 Ω resistive load.

7b

8a

8b

9

10

11a

11b

11c

11d

- A MAU–RD signal consisting of a continuous 20 MHz sine wave with a peak amplitude of 769 mV when measured across a 121 Ω resistive load.
 A MAU–RD signal consisting of a continuous 25 MHz sine wave with a
 - peak amplitude of 1.416 V when measured across a 121 Ω resistive load.
- 11g A MAU–RD signal consisting of a continuous 30 MHz sine wave with a peak amplitude of 2.411 V when measured across a 121 Ω resistive load.
- 12a A MAU–RD signal consisting of a continuous 0.5 MHz sine wave with a peak-to-peak amplitude of 6.1 V.
- 12b A MAU–RD signal consisting of a continuous 1 MHz sine wave with a peak-to-peak amplitude of 6.1 V.
- 12c A MAU–RD signal consisting of a continuous 1.9 MHz sine wave with a peak-to-peak amplitude of 6.1 V.
- 13a A MAU–RD signal consisting of a single cycle 2 MHz sine wave with a peak-to-peak amplitude of 6.1 V preceded and followed by 4 BT of silence.
- 13b A MAU–RD signal consisting of a single cycle 5 MHz sine wave with a peak-to-peak amplitude of 6.1 V preceded and followed by 4 BT of silence.
- 13c A MAU–RD signal consisting of a single cycle 10 MHz sine wave with a peak-to-peak amplitude of 6.1 V preceded and followed by 4 BT of silence.
- 13d A MAU–RD signal consisting of a single cycle 15 MHz sine wave with a peak-to-peak amplitude of 6.1 V preceded and followed by 4 BT of silence.
- 14 A MAU–RD signal consisting of a single packet of 512 bits of pseudorandom data, with only 2.3 BT of SOI following the data, followed by a continuous 10 MHz sine wave with a peak amplitude of 312 mV starting at a phase angle of 180 degrees (i.e., test signal 11c starting in the negative going direction) (see Figure 6-6).
- 15 A MAU–RD signal consisting of a single frame of 512 bits of pseudo-random data. Amplitude of 585 mV peak and maximum edge transition times.
- 16 A MAU–RD signal consisting of repeating frames of 512 bits of pseudorandom data. Amplitude of 585 mV peak, maximum edge transition times and an inter-packet gap of 9.6 µs.
- 17 A 25 V peak-to-peak squarewave with maximum frequency of 500 kHz and with edges no slower than 4 ns (20–80%).
- 18 An AUI–DO signal consisting of a single packet of 512 bits of pseudorandom data, repeating every 1 ms for a total signal duration of 151 ms.
- 19aAn AUI–DO signal consisting of a single frame of 512 bits of Manchester-
encoded 1s.
- 19b An AUI–DO signal consisting of a single frame of 512 bits of Manchesterencoded alternating 1s and 0s.
- 20 An AUI–DO signal consisting of a single frame of 512 bits of pseudorandom data. Amplitude of 159 mV peak and maximum edge transition times.
- 21a A continuous 30 Hz sine wave with a peak amplitude of 3.0 V.
- 21b A continuous 20 kHz sine wave with a peak amplitude of 3.0 V.
- 21c A continuous 40 kHz sine wave with a peak amplitude of 3.0 V.
- 21d A continuous 500 kHz sine wave with a peak amplitude of 200 mV.
- 21e A continuous 1 MHz sine wave with a peak amplitude of 200 mV.
- 21f A continuous 5 MHz sine wave with a peak amplitude of 200 mV.
- 21g A continuous 10 MHz sine wave with a peak amplitude of 200 mV.

22a	A continuous 30 Hz sine wave with a peak amplitude of 3.0 Vac and a dc offset of 2.5 V.
22b	A continuous 20 kHz sine wave with a peak amplitude of 3.0 Vac and a dc offset of 2.5 V.
22c	A continuous 40 kHz sine wave with a peak amplitude of 3.0 Vac and a dc offset of 2.5 V.
22d	A continuous 30 Hz sine wave with a peak amplitude of 3.0 Vac and a dc offset of -2.5 V.
22e	A continuous 20 kHz sine wave with a peak amplitude of 3.0 Vac and a dc offset of -2.5 V.
22f	A continuous 40 kHz sine wave with a peak amplitude of 3.0 Vac and a dc offset of -2.5 V.
22g	A continuous 500 kHz sine wave with a peak amplitude of 200 mVac and a dc offset of 5.3 V.
22h	A continuous 1 MHz sine wave with a peak amplitude of 200 mV ac and a dc offset of 5.3 V.
22i	A continuous 5 MHz sine wave with a peak amplitude of 200 mV ac and a
22j	dc offset of 5.3 V. A continuous 10 MHz sine wave with a peak amplitude of 200 mV ac and
22k	a dc offset of 5.3 V. A continuous 500 kHz sine wave with a peak amplitude of 200 mV ac and
221	a dc offset of -5.3 V. A continuous 1 MHz sine wave with a peak amplitude of 200 mV ac and a
22m	dc offset of -5.3 V. A continuous 5 MHz sine wave with a peak amplitude of 200 mV ac and a
	dc offset of –5.3 V.
22n	A continuous 10 MHz sine wave with a peak amplitude of 200 mV ac and a dc offset of -5.3 V.
23a	An AUI–DO signal consisting of a single frame of 512 bits of Manchester- encoded 1s, with the signal remaining HI for 1.6 BT after the last low-to- high transition (see Figure 6-7). Amplitude of 375 mV peak.
23b	An AUI–DO signal consisting of a single frame of 512 bits of Manchester- encoded 1s, with the signal remaining HI for 1.6 BT after the last low-to-
24a	high transition (see Figure 6-7). Amplitude of 1170 mV peak. An AUI–DO signal consisting of repeating frames of 512 bits of pseudo- random data separated by a 4.7 μ s inter-packet gap with a peak amplitude of 585 mV.
24b	An AUI–DO signal consisting of repeating frames of 512 bits of pseudo- random data separated by a 4.7 μ s inter-packet gap with a peak amplitude of 1.0 V.
24c	An AUI–DO signal consisting of repeating frames of 512 bits of pseudo- random data separated by a 4.7 μ s inter-packet gap with a peak amplitude of 1.5 V.
24d	An AUI–DO signal consisting of repeating frames of 512 bits of pseudo- random data separated by a 4.7 μ s inter-packet gap with a peak amplitude of 2.0 V.
24e	An AUI–DO signal consisting of repeating frames of 512 bits of pseudo- random data separated by a 4.7 μ s inter-packet gap-with a peak amplitude of 2.5 V.
24f	An AUI–DO signal consisting of repeating frames of 512 bits of pseudo- random data separated by a 4.7 μ s inter-packet gap with a peak amplitude of 3.1 V.
25	An AUI–DO signal consisting of repeating frames of 48 bits of data and an inter-packet gap of 50 μ s.



An AUI–DO signal consisting of repeating sequences of preamble and SFD followed by Manchester-encoded 1s lasting 7.5 ms, followed by a $9.6 \ \mu s$ gap.



Figure 6-3 — Typical test signal 7 waveform







Figure 6-5 — Typical test signal 10 waveform



Figure 6-6 — Typical test signal 14 waveform





IEEE Std 1802.3-2001

6.3.2 Common test setups

Common test setup configurations are referenced in the test cases for the MAU. These are described, in general terms, in Figure 6-8 through Figure 6-38. All error terms shall be eliminated or accounted for in the accuracy of the measurement. All load resistors are $\pm 1\%$ unless otherwise noted. In test setups E, F, J, V, AA, BB, and EE, the balance of the test equipment (including matching resistors, if any) should exceed that required of the transmitter or receiver (depending on the test). A cross-reference table listing test setup identifiers and test cases is shown in A1.3.



Figure 6-8 — Test setup A



Figure 6-9 — Test setup B



Figure 6-10 — Test setup C



Figure 6-11 — Test setup D



Figure 6-12 — Test setup E



Figure 6-13 — Test setup F



Figure 6-14 — Test setup G



Figure 6-15 — Test setup H


Figure 6-16 —Test setup I



Figure 6-17 — Test setup J



Figure 6-18 — Test setup K



Figure 6-19 — Test setup L



Figure 6-20 — Test setup M



Figure 6-21 — Test setup N



Figure 6-22 — Test setup O



Figure 6-23 — Test setup P



Figure 6-24 — Test setup Q



Figure 6-25 — Test setup R



Figure 6-26 —Test setup S



Figure 6-27 — Test setup T



Figure 6-28 — Test setup U



Figure 6-29 — Test setup V



Figure 6-30 — Test setup W



Figure 6-31 — Test setup X



Figure 6-32 — Test setup Y



Figure 6-33 — Test setup Z



Figure 6-34 — Test setup AA



Figure 6-35 — Test setup BB



Figure 6-36 —Test setup CC



Figure 6-37 — Test setup DD



Figure 6-38 — Test setup EE

6.3.3 Special test adapters

The test adapters are devices that provide an interface between the test equipment and the MAU under test. The use of these adapters is not mandatory. They are intended to facilitate test implementation. Their exact configuration is dependent on the selected test equipment/instrumentation, the sensitivity of the measurement, cable characteristics, and test method. The contribution of impedance mismatch of adapters and terminations shall be taken into account.

6.3.3.1 Test loads

IFFF

Std 1802.3-2001

These are resistive/inductive terminations in accordance with Standard Reference 14.3.1.2.1 (Figure 14-11) and 7.4.1.1 in ISO/IEC 8802-3.

6.3.3.2 Twisted-pair model (TPM)

This test adapter models the distortion introduced by a link segment. This twisted-pair model shall be constructed in accordance with Standard Reference 14.3.1.2 (Figure 14-7) ISO/IEC 8802-3.

6.3.3.3 The 100 Ω to 50 Ω balun impedance adapter (BAL 1)

This adapter allows a differential signal pair to be properly terminated and matched to a 50 Ω unbalanced impedance. The adapter allows signals on the MAU RD or TD circuits to be monitored or driven by instruments with a 50 Ω impedance. An implementation of the balun may, for example, contain a transformer.

6.3.3.4 The 100 Ω to 100 Ω TPM balun (BAL 2)

This adapter allows the balanced output of the MAU to be matched to the single-ended TPM. If the MAU under test has an output transformer embedded internal to the MAU and directly connected to the MDI, then this balun is not required as the embedded transformer will function as the balun.

6.3.3.5 The 78 Ω to 50 Ω AUI balun (BAL 3)

This adapter allows the balanced MAU DO circuit to be matched to the unbalanced output of the test pattern generator.

6.3.3.6 The 78 Ω to 100 Ω balun (BAL 4)

This adapter allows the unbalanced output of the test pattern generator to be matched to the balanced MAU RD circuit.

6.3.3.7 The 78 Ω balanced-to-balanced 1:1 center-tapped transformer

This transformer allows the application of a common-mode signal to the DO circuit of the MAU.

6.3.3.8 Tester MAU 1

This tester MAU is a conforming MAU.

6.3.3.9 Tester MAU 2

This tester MAU is a conforming MAU with the generation of link test pulses disabled.

6.3.3.10 The 30 Hz to 40 kHz filter (FIL1)

This adapter is used in measuring the ac common-mode output voltage. It is a bandpass Butterworth filter with insertion loss ≤ 0.5 dB at 20 kHz and input impedance ≥ 1 M Ω . The low-pass section shall have Butterworth characteristics consisting of at least 3 poles with a 3 dB cutoff frequency of 40 kHz \pm 5%. The high-pass section shall have Butterworth characteristics consisting of at least 3 poles with a 3 dB cutoff frequency of 30 Hz \pm 5%.

6.3.3.11 The 40 kHz to BR filter (FIL2)

This adapter is used in measuring the ac common-mode output voltage. It is a bandpass Butterworth filter with insertion loss ≤ 0.5 dB at 20 kHz and input impedance ≥ 1 M Ω . The low-pass section shall have Butterworth characteristics consisting of at least 3 poles with a 3 dB cutoff frequency of 10 MHz \pm 5%. The high-pass section shall have Butterworth characteristics consisting of at least 3 poles with a 3 dB cutoff frequency of 40 kHz \pm 5%.

6.3.4 Test equipment capabilities

- a) All test equipment calibration shall be maintained to the manufacturer s specification.
- b) To satisfy the requirements of MAU testing as specified in 6.2, the required functionality of the test instruments is given below.
- c) The use of instruments with equivalent functionality is permitted.
- d) The functionality given below is necessary but not sufficient information. The reader should take into account the selected test setup for complete information.

6.3.4.1 Power supply

Voltage	:	0 V to 20 Vdc
Current	:	2 A
Load Regulation	:	< 0.01%
Line Stability	:	< 0.01%
Ripple and Noise	:	< 1 mV
Output Impedance (dc)	:	$< 5 \text{ m}\Omega$
Temp Coeff (0-45° C)	:	< 0.01%/ °C
Protection ac side	:	Fused
Protection dc side	:	Short circuit and overload

6.3.4.2 Test pattern generator (TPG)

Signaling Rate	:	10 Mb/s nominal
Output	:	Balanced pair as per 7.4.1 of ISO/IEC 8802-3
Output Impedance	:	78 Ω nominal as per 7.4.1 of ISO/IEC 8802-3
Output Jitter	:	$< \pm 0.5$ ns to the MAU under test
Output Amplitude	:	Adjustable, ±1.4 V peak
Output Edge Rate	:	5 ns/V
Data Format	:	Manchester-encoded serial data.
Signaling	:	Continuous stream or variable length packets with preamble, SFD, <i>n</i> bits
		of data (pseudo-random, all 1s, alternating 1s and 0s) and start of idle
Repetition rate	:	Adjustable, single shot to continuous
NOTE —Media Access Co	ntroll	er (MAC)-based implementations of the TPG must not require DO to DI loopback

NOTE —Media Access Controller (MAC)-based implementations of the TPG must not require DO to DI loopback to function properly.

6.3.4.3 Link test pulse generator (LTPG)

Output	:	Balanced pair
Output Impedance	:	100 Ω nominal
Output Amplitude	:	Adjustable
Output Duty Cycle	:	Adjustable
Signaling	:	This is a device that is capable of generating link test pulses in accor- dance with the transmitter waveform for link test pulses shown in Figure 14-12 of ISO/IEC 8802-3.

6.3.4.4 Arbitrary waveform generator (AWG)

Output Amplitude	:	±3.1 V
Output Impedance	:	50 Ω
Sample Resolution	:	5 ns/sample
Record Length	:	256 000 samples, minimum

6.3.4.5 Function generator (FG)

Output Amplitude	:	0 V to 30 V p-p
Output Offset	:	±6 V dc
Output Frequency	:	1 kHz to 21 MHz
Output Impedance	:	50 Ω

6.3.4.6 Spectrum analyzer

Frequency coverage	:	1 MHz to 100 MHz
Reference Level Range	:	-70 to +20 dBm
Frequency Response	:	±1.5 dB (1–100 MHz)
Input Impedance	:	50 Ω

6.3.4.7 Network analyzer

Frequency Range	:	1 MHz to 100 MHz
Frequency Setting	:	1 Hz
Dynamic Range	:	90 dB
Magnitude Accuracy	:	±0.2 dB
Input Impedance	:	50 Ω
Maximum Drive Level	:	≥ +15 dBm

6.3.4.8 Oscilloscope

Туре	:	Digital Real-Time Sampling or Analog Storage
Trigger	:	Internal and External
Number of Channels	:	4
Samples/Channel	:	20 000 points, min. (applies only to digitizing oscilloscopes)
Bandwidth	:	200 MHz single-shot and repetitive
Timebase	:	2 ns/div to 20 ms/div
Amplitude Accuracy	:	±1 mV
Input Coupling	:	AC, DC; 50 Ω or 1 M Ω
Additional Functions	:	Delayed timebase, waveform math functions (A-B, A+B)

6.3.4.9 Differential probe/amplifier (DP)

Bandwidth	:	DC to 100 MHz
CMRR	:	500:1 at 50 MHz
Output Impedance	:	50 Ω or 1 M Ω
Input Impedance	:	1 MΩ

6.3.4.10 High-performance differential probe (HDP)

Bandwidth	:	100 kHz to 100 MHz
CMRR	:	1000:1 (60 dB) at 100 MHz
Output Impedance	:	1 MΩ
Input Impedance	:	1 MΩ

6.3.4.11 Current probe/amplifier (CP)

Bandwidth	:	DC to 50 MHz
Input Current Range	:	1 mA to 10 A DC
Output Impedance	:	50 Ω or 1 M Ω

6.3.4.12 DC ammeter

Current Range	:	100 μ A to 1 μ A DC
Resolution	:	≤ 2 µA

Annex A

(informative)

Reference information

A.1 Type 10BASE-T MAU

A.1.1 State diagram test coverage

Figure A1 through Figure A4 show the test cases used to check the different paths through the state diagrams shown in Figure 14-3 through Figure 14-6 of ISO/IEC 8802-3. This information is provided as an aid to understanding the state machine test procedures.







Figure A2—*signal_quality_error* message test function state diagram coverage



Figure A3 — Jabber function state diagram coverage



Figure A4 — Link integrity test function state diagram coverage

A.1.2 Test signal to test ID cross reference

The following lists the test cases, by Test ID, that use each of the test signals described in 6.3.1.

Test signal	Test case(s)
1	1411.01.01, 1411.01.02, 1411.01.03, 1411.01.04, 1411.01.06, 1411.01.07,
	1411.02.01, 1411.02.02, 1411.02.03, 1411.02.05, 1411.03.01, 1411.03.02,
	1411.03.03, 1411.03.04, 1411.04.01, 1411.04.02, 1411.04.03, 1411.04.04,
	1411.05.01, 1411.05.02, 1411.05.03, 1411.05.04, 1411.07.02, 1411.07.04,
	1411.07.05, 1411.07.06, 1411.08.01, 1411.08.04, 1411.10.02, 1411.10.04,
	1411.10.05, 1411.10.06, 1411.10.09, 1411.10.10, 1411.11.07, 1411.11.08,
	1411.13.01, 1411.13.02, 1411.13.03, 1411.13.04, 1411.13.05
2a	1411.01.05, 1411.08.04
2b–f	1411.01.05
3a	1411.06.01, 1411.06.02, 1411.08.01, 1411.08.03, 1411.13.07
3b	1411.06.01, 1411.06.02, 1411.12.02, 1411.12.03
4	1411.07.01, 1411.10.01, 1411.13.03, 1411.13.07
5	1411.07.06, 1411.08.03, 1411.10.03, 1411.10.14, 1411.15.02
6	1411.10.12, 1411.10.13, 1411.14.05, 1411.14.06
7a, b	1411.11.03
8a, b	1411.11.03
9	1411.11.03
10	1411.11.03
11a-g	1411.11.04
12a–c	1411.11.04
13a–d	1411.11.04
14	1411.11.02
15	1411.11.06
16	1411.11.08
17	1411.11.06
18	1411.08.04
19a	1411.04.05, 1411.04.06, 1411.15.05
19b	1411.04.05, 1411.04.06
20	1411.14.02
21a-g	1411.14.05
22a–n	1411.14.06
23a, b	1411.14.03, 1411.14.07
24a–f	1411.02.04
25	1411.13.03
26	1411.06.03

A.1.3 Test setup to test ID cross reference

The following lists the test cases, by test ID, that use each of the test setups described in 6.3.2.

Test setup	Test case(s)
А	1411.10.04, 1411.10.05, 1411.10.12, 1411.10.15, 1411.14.08, 1411.15.01,
	1411.15.02, 1411.15.03, 1411.15.04
В	1411.01.01, 1411.01.02, 1411.01.03, 1411.01.04, 1411.01.05, 1411.01.06,
	1411.01.07, 1411.03.01, 1411.03.02, 1411.03.03, 1411.03.04, 1411.05.01,
	1411.05.02, 1411.05.03, 1411.06.03, 1411.07.01, 1411.07.02, 1411.07.04,
	1411.08.04, 1411.10.02, 1411.10.13, 1411.11.07, 1411.14.02
С	1411.06.01, 1411.06.02, 1411.08.03, 1411.12.02, 1411.12.03
D	1411.10.06, 1411.14.03, 1411.14.07
E	1411.10.08, 1411.10.10
F	1411.10.09
G	1411.10.11
Η	1411.02.04, 1411.11.08
Ι	1411.11.05
J	1411.11.06
K	1411.11.02, 1411.11.03, 1411.11.04
L	1411.02.01, 1411.02.02, 1411.02.03, 1411.02.05
Μ	1411.04.01, 1411.04.05, 1411.04.06, 1411.08.04
Ν	1411.05.04, 1411.07.05, 1411.07.06, 1411.08.01, 1411.08.04
0	1411.04.02, 1411.04.03, 1411.04.04
Р	1411.08.01
Q	1411.10.07
R	1411.10.01
S	1411.11.01
Т	1411.10.03
U	1411.13.01, 1411.13.02
V	1411.13.05
W	1411.13.04
Х	1411.13.06, 1411.13.07, 1411.14.09
Y	1411.14.04, 1411.16.01
Z	1411.14.05, 1411.14.06
AA	1411.10.14
BB	1411.11.09
CC	1411.09.01
DD	1411.09.02
EE	1411.13.03